



## STAGE 2 © STA. 267+59 LOOKING NORTH NO SCALE

## LEGEND

- 1 PAVEMENT REMOVAL
- (2) EARTH EXCAVATION
- 3 REMOVAL OF EXISTING STRUCTURES
- 4) STRUCTURE EXCAVATION
- (5) REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL
- 6 PRECAST CONCRETE BOX CULVERT 7'x3'
- (7A) HMA BINDER COURSE IL-19mm, N7O, 8<sup>1</sup><sub>2</sub>" (IN 3 LIFTS)
- (7B) HMA SURFACE COURSE MIX D, N70,  $1_2''$
- 8 BITUMINOUS MATERIALS (PRIME COAT)
- 9 COARSE AGGREGATE BACKFILL (SPECIAL)
- (10) COMPOST FURNISH AND PLACE 4"
- 11) TEMPORARY CONCRETE BARRIER
- (12) PAVEMENT MARKING TAPE, TYPE III, 4" WHITE
- (13) DRUM WITH STEADY BURNING LIGHT
- (14) CA 7

## NOTE:

HMA BINDER AND SURFACE COURSE TO BE PAID FOR AS CLASS D PATCHES, TYPE IV, 10" IN SQ.YD.

	DESIGNED - MJY	
	DRAWN - ZDA	REVISED
CONSULTING ENGINEERS 1560 WALL ST, SUITE 222	CHECKED - MJY	REVISED
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100	DATE - 01/21/2009	REVISED

STATE	OF	ILLINOIS
DEPARTMENT (	OF 1	<b>TRANSPORTATION</b>

SCALE: NONE

STAGING TYPICAL SECTIONS US ROUTE 30		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		349	15 T-1	WILL	20	5	
		D-91-215-09		CONTRACT	NO. 6	OF69	
	SHEET NO. 5 OF 20 SHEETS	STA. 267+35 TO STA. 267+83	FED. RC	FED. ROAD DIST. NO ILLINOIS FED. AID PROJECT			