


NOTE A - EXISTING COMED POLE MOUNTED TRANSFORMER, 25KVA.

NOTE B - COMED METER AND SERVICE BOX MOUNTED ON WOODEN POLE, SEE SHEET 12, FOR SERVICE ENTRANCE POLE DETAIL

**TEMPORARY LIGHTING NOTES**

1. TEMPORARY LUMINAIRE, SODIUM VAPOR, 400 WATT, HORIZONTAL-MOUNT, PHOTO-CELL, TYPE II DISTRIBUTION.
2. TEMPORARY LIGHTING TO BE REMOVED AS DIRECTED BY IDOT WHEN ROADWAY CONSTRUCTION IS COMPLETE.
3. ALL SYSTEMS ARE TO BE REQUIRED TO REMAIN OPERATIONAL DURING STAGED CONSTRUCTION.
4. GROUND EVERY THIRD POLE WITH TEMPORARY LUMINAIRE UNLESS NOTED OTHERWISE ON PLAN.
5. TEMPORARY POLES SHALL BE 60 FEET UNLESS OTHERWISE NOTED.

*Chris Hester*  
 EITP 11/30/09



**LONCO, INC.**  
 CONSULTING ENGINEERS  
 1560 WALL ST., SUITE 222  
 NAPERVILLE, ILLINOIS 60563 PH: (630) 571-9100

DESIGNED - MJY	REVISED -
DRAWN - ST	REVISED -
CHECKED - MJY	REVISED -
DATE - 01/16/2009	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**TEMPORARY LIGHTING PLAN  
 US ROUTE 30**

SCALE: 1" = 20' SHEET NO. 10 OF 20 SHEETS STA. 267+35 TO STA. 267+83

F.A.P. RTE. 349	SECTION 15 T-1	COUNTY WILL	TOTAL SHEETS 20	SHEET NO. 10
D-91-215-09			CONTRACT NO. 60F69	
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				