

I-290 WESTBOUND-OUTSIDE SHOULDER

LOCATIONS FOR I-290	RUMBLE STRIP LENGTH (FT)	SHOULDER SURFACE TYPE	COUNTY	LOCATIONS FOR I-290	REPAIR LENGTH (FT)	SURFACE TYPE	COUNTY
HIGGINS TO BIESTERFIELD	10560	CONCRETE	COOK	CENTRAL TO LARAMIE	166	CONCRETE	COOK
BIESTERFIELD TO THORNDALE	3168	CONCRETE	COOK	CENTRAL TO LARAMIE	2686	HMA	COOK
BIESTERFIELD TO THORNDALE	528	HMA	DUPAGE	LARAMIE TO CICERO	2122	HMA	COOK
THORNDALE TO I-355	8976	HMA	DUPAGE	CICERO TO INDEPENDENCE	6000	HMA	COOK
I-355 TO I-83	16896	HMA	DUPAGE	INDEPENDENCE TO KEDZIE	3600	HMA	COOK
I-83 TO YORK	6045	HMA	DUPAGE	KEDZIE TO WESTERN	4172	HMA	COOK
YORK TO NORTH	16527	HMA	DUPAGE	WESTERN TO DAMEN	1272	HMA	COOK
NORTH TO ST. CHARLES	2128	HMA	COOK	DAMEN TO ASHLAND	2072	HMA	COOK
ST. CHARLES TO I-294	5280	HMA	COOK	ASHLAND TO LOOMIS	472	HMA	COOK
I-294 TO MANNEHEIM	10428	HMA	COOK	LOOMIS TO I-90/94	3030	HMA	COOK
MANNEHEIM TO 25TH	2492	HMA	COOK				
25TH TO 17TH	2414	HMA	COOK				
17TH TO 1ST	5070	HMA	COOK				
1ST TO DESPLAINES	2549	CONCRETE	COOK				
1ST TO DESPLAINES	2231	HMA	COOK				
DESPLAINES TO HARLEM	1773	CONCRETE	COOK				
DESPLAINES TO HARLEM	1257	HMA	COOK				
HARLEM TO AUSTIN	8290	CONCRETE	COOK				
AUSTIN TO CENTRAL	1500	CONCRETE	COOK				

FILE NAME =	USER NAME = mossse	DESIGNED -	REVISED -
ct:\pw_work\PWIDOT\MOSSSE\0107599\sh_rdy.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2008-075 1	COOK/DUPAGE	8	5
CONTRACT NO. 60F76				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				