



TEMPORARY INTERCONNECT PLAN LEGEND

- CONTROLLER
- SERVICE INSTALLATION
- EXISTING HANDHOLE
- EXISTING CONDUIT
- AERIAL INTERCONNECT CABLE - 3 PAIR #18
- WOOD POLE CLASS 4 30 FT. MINIMUM
- SYSTEM
- EXISTING INTERSECTION

CONSTRUCTION NOTE:
 ① EXISTING INTERCONNECT CONDUIT AND SYSTEM HANDHOLES SHOWN ARE TO BE UTILIZED FOR PERMANENT INTERCONNECT.

RESTORATION OF WORK AREA. RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDING IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

PROFILE	REVIEWED	DATE
NOTE BOOK	GRABER'S CHECKED	
	STRUCTURE NOTATION CHVD	
PLAN	SURVEYED	BY
	ALIGNMENT CHECKED	
	RT. OF WAY CHECKED	
	GRID FILE NAME	

CHRISTOPHER B. BURKE ENGINEERING LTD.
 9575 West Higgins Road, Suite 600
 Blue Bell, PA 19380
 (610) 283-0500

FILE NAME = N:\dot\080840\Task G-P IL 50\Tr-offic\INT6-temp_IL50.dgn	USER NAME = FPACIONE	DESIGNED - ABR	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TEMPORARY INTERCONNECT PLAN		F.A.P. RTE. 350	SECTION 2008-080-1	COUNTY COOK	TOTAL SHEETS 76	SHEET NO. 57	
	PLLOT SCALE = 50'	CHECKED - MJT	REVISED -		IL. ROUTE 50 (CICERO AVE.) FROM 39th ST. (PERSHING RD.) TO ROOSEVELT RD., CICERO, ILLINOIS		CONTRACT NO. 60F82					
	PLLOT DATE = 12/10/2008	DATE -	REVISED -		SCALE: 1"= 50'		SHEET NO. OF SHEETS STA. TO STA.					
							ILLINOIS FED. AID PROJECT					