

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5				
40600300	AGGREGATE (PRIME COAT)	TON	11	11				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	300	300				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	115	115				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	531	531				
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SO YD	510	510				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	4910	4910				
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	30	30				
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	75	75				
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1300	1300				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	146	146				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3960	3960				
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	740	740				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	300	300				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	290	290				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	70	70				

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1730	1730				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	146	146				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1900	1900				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	290	290				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	70	70				
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B LINE 4" (INLAID)	FOOT	80	80				
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B LINE 5" (INLAID)	FOOT	470	470				
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B LINE 6" (INLAID)	FOOT	300	300				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	60	60				
78300100	PAVEMENT MARKING REMOVAL	SO FT	434	434				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	60	60				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	150	150				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	7	7				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev.

12/23/2008 10:45:30 AM \\P:\DOT\PROJECTS\2008\60F68\60F68-070-RS\SUMMARY OF QUANTITIES.dgn