



PRE-STAGE TYPICAL  
(LOOKING EAST)

**PRE-STAGE WORK**

TEMPORARY PAVEMENT SHALL BE CONSTRUCTED BEFORE TRAFFIC STAGING  
 THE THICKNESS OF THE TEMPORARY PAVEMENT SHALL BE 10"  
 (2" HMA SURFACE COURSE, MIX "D", N 50 AND 8" HMA BINDER, IL-19 mm)  
 TEMPORARY PAVEMENT SHALL BE REMOVED DURING STAGE II CONSTRUCTION  
 AND BE REPLACED WITH HOT-MIX ASPHALT SHOULDER AS SHOWN IN PLANS

FILE NAME =	USER NAME = smthkl	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PRE-STAGE IL 68 OVER SPRING CREEK - S.N. 016-2811</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et\p\work\PMIDOT\SMITHKL\dms92925\design.ea.dgn		DRAWN -	REVISED -			343	631T	COOK	33	9	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 62710					
	PLOT DATE = 12/23/2008	DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	