

## SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	08-00085-00-RS	DUPAGE	13	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
<b>CONTRACT NO. 63064</b>				

ITEM NO.	ITEMS	UNIT	1000 QUANTITY	SFTY-1B NON-PARTICIPATING	TOTAL
25200200	SUPPLEMENTAL WATERING	UNIT	20	0	20
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	100	0	100
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200	0	200
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	700	0	700
40600300	AGGREGATE (PRIME COAT)	TON	14	0	14
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	604	0	604
40600895	CONSTRUCTING TEST STRIP	EACH	1	0	1
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	20	0	20
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1409	0	1409
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	300	0	300
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	100	1000	1100
42400800	DETECTABLE WARNINGS	SQ FT	100	0	100
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	14000	0	14000
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	400	0	400
44000600	SIDEWALK REMOVAL	SQ FT	100	1000	1100
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	0	500
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	14000	0	14000
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	0	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	15	0	15
67100100	MOBILIZATION	L SUM	1	0	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L. SUM	1	0	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L. SUM	1	0	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L. SUM	1	0	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L. SUM	1	0	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1700	0	1700
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	567	0	567
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	268	0	268
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6000	0	6000
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4000	0	4000
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	230	0	230
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	330	0	330
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	600	0	600
XX000406	BRICK PAVER REMOVAL AND REPLACEMENT	SQ FT	500	0	500
XX000667	SUB-BASE GRANULAR MATERIAL, TYPE B 2"	SQ YD	10	120	130
XX003535	AGGREGATE BASE COURSE, TYPE B, 2"	SQ YD	300	0	300
Z0017500	DRAINAGE & UTILITY STRUCTURE ADJUSTMENT (SPECIAL)	EACH	70	0	70
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L. SUM	1	0	1
XX00112	CLASS D PATCHES, SPECIAL, 12-INCHES	SQ YD	1400	1400	2800

• SPECIALTY ITEMS

SURVEYED BY DATE  
 PLOTTED BY DATE  
 NOTE BOOK NO. FILE NAME

**CHRISTOPHER B. BURKE** ENGINEERING LTD.  
 9575 West Higgins Road, Suite 600  
 Rosemont, Illinois 60018  
 (847) 823-0500



PROFILE SURVEYED BY DATE  
 CHECKED BY DATE  
 NOTE BOOK NO. NOTATION CHKD

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES  SCALE NTS DATE 12/1/2008  DRAWN BY MYG CHECKED BY KJB