

GENERAL NOTES

- STANDARD SPECIFICATIONS: ALL ITEMS OF WORK SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE ARTICLES OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, ADOPTED JANUARY 1, 2007 BY THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- MATERIAL CERTIFICATION: THE CONTRACTOR IS REMINDED THAT ALL MATERIALS USED IN THE PROJECT MUST BE STATE INSPECTED. SUBMIT INSPECTION REPORTS TO THE ENGINEER TO AVOID DELAY IN FINAL INSPECTION OF THE PROJECT.
- PRESERVATION OF TREES AND SHRUBS: EXISTING TREES AND SHRUBS SHALL BE PROTECTED WITH SNOW FENCING AS DIRECTED BY THE ENGINEER DURING THE CONSTRUCTION OF THE IMPROVEMENT. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE COST OF THE PROJECT.
- EXISTING PAVEMENT: EXISTING PAVEMENT, DRIVEWAY PAVEMENT, SIDEWALK AND CURB AND GUTTER THAT IS TO REMAIN IN PLACE SHALL BE SAW-CUT TO PROVIDE A NEAT VERTICAL FACE BETWEEN THE PROPOSED AND EXISTING SURFACES.
- SIGNS: THE CONTRACTOR SHALL NOT REMOVE OR RELOCATE ANY PARKWAY SIGNS. HE SHALL NOTIFY THE ENGINEER WITHIN 24 HOURS TO HAVE THE PARKWAY SIGN REMOVED BY THE VILLAGE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE THAT MAY OCCUR TO THE SIGNS UNTIL THEY ARE REMOVED BY THE VILLAGE.

LEGEND

SYMBOL	DESCRIPTION
⊙	EXISTING MANHOLE
○	EXISTING INLET
□	UTILITY BOX
⊕	EXISTING STREETLIGHT/UTILITY POLE
⊗	FIRE HYDRANT
☼	EXISTING TREE
▣	DETECTABLE WARNING
▨	CURB REMOVAL & REPLACEMENT
▩	SIDEWALK REMOVAL (NO REPLACEMENT)

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE SFTY-1B		
				BUSSE RD	GOLF RD	LINNEMAN RD
20200100	EARTH EXCAVATION	CU YD	315	125	80	110
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1165	425	370	370
25200100	SODDING	SQ YD	1165	425	370	370
35101600	AGGREGATE BASE COURSE, TYPE B, 4"	SQ YD	1010	410	245	355
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8120	3170	2075	2875
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	300	0	150	150
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	645	495	0	150
42400800	DETECTABLE WARNINGS	SQ FT	96	64	0	32
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	105	55	15	35
44000600	SIDEWALK REMOVAL	SQ FT	600	600	0	0
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	120	80	0	40
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	65	35	10	20
48301000	PROTECTIVE COAT	SQ YD	1010	410	245	355
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2	0	0
67100100	MOBILIZATION	L SUM	1	0.33	0.33	0.33
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	0.33	0.33	0.33