

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE						
					I000	SFTY-1D	Y002-1C	Y003	Y030-1E	Y031	Y080
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2200	2200						
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2						
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	950	950						
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1850	1850						
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	22100	22100						
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	700	700						
	44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	10	10						
	44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	25	25						
	44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	450	450						
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	36	36						
	60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1						
	60255500	MANHOLES TO BE ADJUSTED	EACH	4	4						
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	680	680						
	67100100	MOBILIZATION	L SUM	1	1						
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1						
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1						
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3500	3500						
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7000	7000						
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	20	20						
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	900	900						

* - INDICATES SPECIALTY ITEMS

FILE NAME = 07585-QUAN-01 - IDOT P01	USER NAME =	DESIGNED -- RS	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	201ST STREET RESURFACING TORRENCE AVENUE TO BURNHAM AVENUE SUMMARY OF QUANTITIES & GENERAL NOTES			F.A.U. RTE. 1703	SECTION 08-00025-00-RS	COUNTY COOK	TOTAL SHEETS 010	SHEET NO. 002
	PLOT SCALE =	CHECKED -- RS	REVISED --		SCALE: NONE	SHEET NO. 002 OF 010 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT M-9003 (132)	CONTRACT NO. 63110
	PLOT DATE = 12-18-08	DRAWN -- PS	REVISED --									
		CHECKED -- PS	REVISED --									