

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY.	STP FUNDS	CMAQ FUNDS
54214743	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 48"	EACH	1	1	
54248180	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 48"	EACH	1	1	
55019500	STORM SEWERS, TYPE 1, RCP, CLASS IV, 12"	FOOT	13	13	
55019600	STORM SEWERS, TYPE 1, RCP, CLASS IV, 15"	FOOT	108	108	
55019900	STORM SEWERS, TYPE 1, RCP, CLASS IV, 24"	FOOT	115	115	
55021600	STORM SEWERS, TYPE 2, RCP, CLASS III, 12"	FOOT	944	944	
55021700	STORM SEWERS, TYPE 2, RCP, CLASS III, 15"	FOOT	341	341	
55021800	STORM SEWERS, TYPE 2, RCP, CLASS III, 18"	FOOT	217	217	
55022000	STORM SEWERS, TYPE 2, RCP, CLASS III, 24"	FOOT	581	581	
55022200	STORM SEWERS, TYPE 2 RCP, CLASS III 30"	FOOT	106	106	
55022500	STORM SEWERS, TYPE 2, RCP, CLASS III, 42"	FOOT	71	71	
55022600	STORM SEWERS, TYPE 2, RCP, CLASS III, 48"	FOOT	374	374	
55034200	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 23, RISE 14	FOOT	25	25	
55034800	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 60, RISE 38	FOOT	447	447	
55100300	STORM SEWER REMOVAL, 8"	FOOT	126	126	
55100500	STORM SEWER REMOVAL, 12"	FOOT	467	467	
55100700	STORM SEWER REMOVAL, 15"	FOOT	515	515	
55101200	STORM SEWER REMOVAL, 24"	FOOT	63	63	
* 56106400	ADJUSTING WATER MAIN 8"	FOOT	120	120	
* 56106500	ADJUSTING WATER MAIN 10"	FOOT	40	40	
* 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	200	200	
* 56300300	ADJUSTING WATER SERVICE LINES	FOOT	200	200	
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1	
* 56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	9	9	
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	1	1	
60201340	CATCH BASIN, TYPE A, 4' DIA., TYPE 24 FRAME AND GRATE	EACH	5	5	
60202710	CATCH BASINS, TYPE A, 4'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	4	4	

REVISIONS	
NAME	DATE

CITY OF CRYSTAL LAKE  
  
ERICK STREET (FAU 0125)  
SUMMARY OF QUANTITIES

SCALE: NONE  
DATE: DECEMBER 15, 2008  
DRAWN BY: MJV  
CHECKED BY: DES

