

80% FED  
20% STATE

Pay Code	Item	Unit	Quantity	Mainline	Relocate Lighting	Concrete Barrier
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	222.00	222.00		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	255.00	255.00		
20100500	TREE REMOVAL, ACRES	ACRE	4.00	4.00		
20200100	EARTH EXCAVATION	CU YD	△ 95,150.00	95,150.00		
20201006	GRADING AND SHAPING SHOULDERS	UNIT	114.00	114.00		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	8.00	8.00		
20800150	TRENCH BACKFILL	CU YD	△ 795.00	795.00		
* 25000210	SEEDING, CLASS 2A	ACRE	30.75	30.75		
* 25000310	SEEDING, CLASS 4	ACRE	3.25	3.25		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3,020.00	3,020.00		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3,020.00	3,020.00		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3,020.00	3,020.00		
● 25000750	MOWING	ACRE	20.00	20.00		
* 25100115	MULCH, METHOD 2	ACRE	3.25	3.25		
* 25100630	EROSION CONTROL BLANKET	SQ YD	82,510.00	82,510.00		
* 25100900	TURF REINFORCEMENT MAT	SQ YD	9,798.00	9,798.00		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	12,380.00	12,380.00		
28000300	TEMPORARY DITCH CHECKS	EACH	358.00	358.00		
28000400	PERIMETER EROSION BARRIER	FOOT	10,295.00	10,295.00		
28000500	INLET AND PIPE PROTECTION	EACH	35.00	35.00		
28100101	STONE RIPRAP, CLASS A1	SQ YD	2,077.00	2,077.00		
28100105	STONE RIPRAP, CLASS A3	SQ YD	△ 1,365.00	1,365.00		
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,324.00	1,324.00		
28100109	STONE RIPRAP, CLASS A5	SQ YD	753.00	753.00		
28200200	FILTER FABRIC	SQ YD	△ 10,989.00	10,989.00		
28300470	AGGREGATE DITCH 12"	SQ YD	5,805.00	5,805.00		
28400100	GABIONS	CU YD	11.00	11.00		
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	△ 139,473.00	139,473.00		
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SQ YD	11,812.00	11,812.00		
31100965	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SQ YD	25,517.00	25,517.00		

● 100% STATE \* SPECIALTY ITEM

△ REVISED  
2-23-09

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\grantpm\dms34287\d88403covr.dgn		DRAWN -	REVISED -					80	(81-1) R-1	ROCK ISLAND	292	3
PLOT SCALE = 100,000' / IN.		CHECKED -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO. 64933		
PLOT DATE = Mon Dec 15 09:18:39 2008		DATE -	REVISED -					FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		