

80% FED.
20% STATE

Pay Code	Item	Unit	Quantity	Mainline	Relocate Lighting	Concrete Barrier
				J000		
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	1,930.00	1,930.00		
31103000	SUB-BASE GRANULAR MATERIAL (SPECIAL)	SQ YD	42,195.00	42,195.00		
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	163,474.00	163,474.00		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.60	0.60		
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	6.90	6.90		
40600300	AGGREGATE (PRIME COAT)	TON	37.30	37.30		
40600535	LEVELING BINDER (HAND METHOD), N70	TON	15.00	15.00		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	34.00	34.00		
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	1,340.00	1,340.00		
40600895	CONSTRUCTING TEST STRIP	EACH	1.00	1.00		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	281.00	281.00		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	160.00	160.00		
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	48.00	48.00		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	951.00	951.00		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	78.00	78.00		
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,360.00	1,360.00		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	214.00	214.00		
42000551	PORTLAND CEMENT CONCRETE PAVEMENT 12 1/2" (JOINTED)	SQ YD	10,377.00	10,377.00		
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	258.00	258.00		
42101300	PROTECTIVE COAT	SQ YD	59,185.00	59,185.00		
42100350	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 12 1/2"	SQ YD	117,811.00	117,811.00		
42100950	PAVEMENT REINFORCEMENT 12 1/2"	SQ YD	117,811.00	117,811.00		
42101020	WIDE FLANGE BEAM TERMINAL JOINT COMPLETE 24'	EACH	2.00	2.00		
42001700	FURNISH PROFILOGRAPH	L SUM	1.00	1.00		
44000100	PAVEMENT REMOVAL	SQ YD	6,639.00	6,639.00		
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	23,929.00	23,929.00		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,200.00	1,200.00		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,840.00	1,840.00		
44000700	APPROACH SLAB REMOVAL	SQ YD	172.00	172.00		
44001980	CONCRETE BARRIER REMOVAL	FOOT	1,466.00	1,466.00		

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -
c:\pwwork\pwwork\grantpm\dms34287\d08403cvt.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

REVISD 2/23/09

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(81-1) R-1	ROCK ISLAND	292	4
CONTRACT NO. 64933				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				