

Schedule of Quantities

Pay Item #	Description	Unit	Comments
63100167	Traffic Barrier Terminal, Type 1 (Special), Tangent	Each	
	<u>Location</u>		
	2519 + 09.26 RT	1	
	2522 + 10.09 RT	1	
	2519 + 51.91 LT	1	
	2522 + 52.75 LT	1	
	Total =	4	
63200310	Guardrail Removal	Foot	
	<u>Location</u>		
	2474 + 67.9 - 2475 + 95.9 RT	128.35	
	2474 + 91.3 - 2476 + 19.2 LT	128.2	
	2519 + 29.76 - 2522 + 31.69 RT	319.75	
	2519 + 29.69 - 2522 + 31.61 LT	322.06	
	Total =	898.36	
63500105	Delineators	Each	
	<u>Location</u>		
	2472 + 70.3 57.2' LT	1	
	2472 + 70.3 61.8' LT	1	
	2472 + 70.3 45' LT	1	
	2472 + 79.7 57.2' LT	1	
	2472 + 79.7 61.8' LT	1	
	2519 + 09.26 RT	1	
	2519 + 51.91 LT	1	
	2520 + 74.7 34.8' RT	1	
	2520 + 87.3 34.8' LT	1	
	2522 + 10.09 RT	1	
	2522 + 52.75 LT	1	
	Total =	11	
66600105	Furnishing and Erecting Right-of-Way Markers	Each	
	<u>Location</u>		
	2470 + 00 40' LT	1	
	2471 + 00 40' RT	1	
	2472 + 00 50' RT	1	
	2472 + 00 55' LT	1	
	2472 + 50 95' RT	1	
	2472 + 50 85' LT	1	
	2473 + 00 95' RT	1	
	2473 + 00 85' LT	1	
	2474 + 00 65' RT	1	
	2474 + 00 60' LT	1	
	2476 + 00 60' RT	1	
	2477 + 82.89 55' RT	1	
	2478 + 00 40' RT	1	
	2517 + 00 40' RT	1	
	2517 + 00 40' LT	1	
	2518 + 00 50' RT	1	
	2518 + 00 50' LT	1	
	2520 + 00 90' LT	1	
	2520 + 25 120' LT	1	
	2520 + 50 100' RT	1	
	2520 + 75 120' LT	1	
	2521 + 00 90' LT	1	
	2521 + 00 100' RT	1	
	2523 + 00 50' RT	1	
	2523 + 00 55' LT	1	
	2524 + 00 40' RT	1	
	2524 + 00 45' LT	1	
	Total =	27	
66700305	Permanent Survey Markers, Type II	Each	
	<u>Location</u>		
	To be determined by contractor @ both working areas	4	
	Total =	4	

Pay Item #	Description	Unit	Comments
70106500	Temporary Bridge Traffic Signals	Each	
	<u>Location</u>		
	2517 + 73.3 RT		
	2517 + 98.3 LT		
	2524 + 14.1 RT		
	2524 + 39.1 LT		
	Total =	1	
70106700	Temporary Rumble Strips	Each	
	To be placed according to Traffic Control and Protection, Standards 701316-03, 701321-09	6	
	Total =	6	
70300220	Temporary Pavement Marking - Line 4"	Foot	
	<u>Location</u>		
	2472 + 26.34-2476 + 01.5 19.5' LT (Stage 1)	375.0	
	2516 + 93.1 -2523 + 46.5 (Stage 1)	656.0	
	2519 + 09.2 -2523 + 90.3 (Stage 1)	381.0	
	2518 + 14.9 - 2524 + 35.8 (Stage 2)	623.0	
	2518 + 54.5 - 2522 + 64.6 (Stage 2)	410.0	
	Total =	2445	
70300280	Temporary Pavement Marking - Line 24"	Foot	
	<u>Location</u>		
	2517 + 22.3	13	
	2524 + 90.1	13.6	
	Total =	26.6	
70301000	Workzone Pavement Marking Removal	Sq. Ft.	
	<u>Location</u>		
	2472 + 26.34-2476 + 01.5 19.5' LT (Stage 1)	125.0	
	2516 + 93.1 -2523 + 46.5 (Stage 1)	218.7	
	2519 + 09.2 -2523 + 90.3 (Stage 1)	127.0	
	2518 + 14.9 - 2524 + 35.8 (Stage 2)	207.7	
	2518 + 54.5 - 2522 + 64.6 (Stage 2)	136.7	
	2516 + 83.1	26	
	2524 + 45.8	27.2	
	Total =	868.2	
70400100	Temporary Concrete Barrier	Foot	
	<u>Location</u>		
	2518 + 67.4 - 2522 + 14.9 (Stage 1)	350	
	Total =	350	
70400200	Relocate Temporary Concrete Barrier	Foot	
	<u>Location</u>		
	2519 + 54.9 - 2522 + 79.3 (Stage 2)	325	
	Total =	325	
78001110	Paint Pavement Marking - Line 4"	Foot	
	<u>Location</u>		
	2472 + 29.3 - 2475 + 98.5 LT	369	
	2472 + 54.3 - 2472 + 95.7 Centerline	10	
	2472 + 54.3 - 2472 + 95.7 RT	41	
	2475 + 13.0 - 2475 + 73.5 Centerline	20	
	2475 + 13.0 - 2475 + 73.5 RT	61	
	2517 + 22.3 - 2524 + 00 Centerline	170	
	2517 + 22.3 - 2523 + 32 RT	610	
	2518 + 05.2 - 2524 + 79.1 LT	674	
	Total =	3910	2 Applications
78200410	Guardrail Markers, Type A	Each	
	<u>Location</u>		
	As per State Standard 635006-02	16	
	Total =	16	