

# Schedule of Quantities

Pay Item #	Description	Unit	Comments
78201000	Terminal Marker - Direct Applied	Each	
<b>Location</b>			
2519 + 09.26	RT	1	
2522 + 10.09	RT	1	
2519 + 51.91	LT	1	
2522 + 52.75	LT	1	
	<b>Total =</b>	<b>4</b>	
78300100	Pavement Marking Removal	Sq. Ft.	
<b>Location</b>			
2472 + 26.3 - 2476 + 01.5	LT	125.1	
2516 + 83.1 - 2524 + 45.8	Centerline	254.2	
2516 + 83.1 - 2523 + 46.5	RT	221.1	
2518 + 14.9 - 2524 + 45.8	LT	210.3	
	<b>Total =</b>	<b>810.7</b>	
X0323660	Drop Box No.1	Each	
<b>Location</b>			
2472 + 75.0		1	
	<b>Total =</b>	<b>1</b>	
X0712400	Temporary Pavement	Sq. Yd.	
<b>Location</b>			
2472 + 08.3 - 2476 + 19.5 (Stage 1)		304.4	
2472 + 54.3 - 2472 + 95.7 (Stage 2)		31.8	
2475 + 13 - 2475 + 73.5 (Stage 2)		47.1	
	<b>Total =</b>	<b>383.3</b>	
Z0023600	Filling Existing Culvert	Each	
<b>Location</b>			
2473 + 27.2		1	
	<b>Total =</b>	<b>1</b>	
Z0030250	Impact Attenuators, Temporary (Non-Directive), Test Level 3	Each	
<b>Location</b>			
2518 + 67.0 & 2522 + 16.5 (Stage 1)		2	
	<b>Total =</b>	<b>2</b>	
Z0030350	Impact Attenuators, Relocate (Non-Directive), Test Level 3	Each	
<b>Location</b>			
2519 + 53.0 & 2522 + 80.0 (Stage 2)		2	
	<b>Total =</b>	<b>2</b>	