

# LETTERING FOR NAME PLATE

STATION  
BUILT 200 BY  
STATE OF ILLINOIS  
RTE. SEC.  
FA PROJECT  
LOADING HS 20  
STR. NO.

SEE STD. 515001

STATION	STRUCTURE NO.
2472+75	050-1004

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES) UNLESS OTHERWISE NOTED.

REVISED - 11-01-07

**LETTERING FOR NAME PLATE 89.4**

# TREE REPLACEMENT SCHEDULE

CODE NUMBER	SCIENTIFIC NAME	COMMON NAME	SIZE	UNIT	QUANTITY
C2001548	Cornus Racemosa	Grey Dogwood	4' Height	Each	20
A2006714	Quercus Macrocarpa	Bur Oak	1 3/4" Caliper	Each	14

\* LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT  
 \* MULCH SHALL BE HARDWOOD WOOD CHIPS, 5 FOOT DIAMETER, 4 INCHES THICK WITH WEED BARRIER  
 \* SOME OF THE REPLACEMENT TREES SHALL BE PLANTED ALONG THE STREAM CORRIDOR WITHIN THE PROJECT LIMITS AS REQUESTED BY BDE  
 \* IF NEEDED THE ALTERNATE PLANTING SITE SHALL BE AT THE I-39/CHICAGO INTERCHANGE

REVISED - 8-10-05

**TREE REPLACEMENT SCHEDULE 90.4**

# STOP LINE SIGN FOR TEMPORARY SIGNALS



SIZE: 600(24) x 600(24)  
 100(4) CAPITAL LETTERS - BLACK  
 13(1/2) BORDER - BLACK  
 WHITE REFLECTIVE - TYPE AP  
 HIGH INTENSITY PRISMATIC SHEETING

**GENERAL NOTE:**  
 THIS SIGN SHALL BE INSTALLED AT THE STOP LINE AS DIRECTED BY ENGINEER.  
 ALL DIMENSIONS ARE IN MILLIMETERS (INCHES) UNLESS OTHERWISE NOTED.

REVISED - 1-22-07

**STOP LINE SIGN FOR TEMPORARY SIGNALS 99.4**

REVISED -	<b>REGION 2 / DISTRICT 2 STANDARD</b>	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
REVISED -		1177	111T	LASALLE	59	41
REVISED -		CONTRACT NO. 64A07				
REVISED -		SCALE: 50.0000' / IN		SHEET NO. OF SHEETS		STA. TO STA.