

SUMMARY OF QUANTITIES

80% FED
20% STATE

ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	BRIDGE X081-2A
20200100	EARTH EXCAVATION	CU YD	295	295	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	30	30	
20300100	CHANNEL EXCAVATION	CU YD	30	30	
20400800	FURNISHED EXCAVATION	CU YD	990	990	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	145		145
25000210	SEEDING, CLASS 2A	ACRE	0.84	0.84	
** 25000750	MOWING	ACRE	0.84	0.84	
25100630	EROSION CONTROL BLANKET	SQ YD	4,037	4,037	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	336	336	
28000300	TEMPORARY DITCH CKECKS	EACH	2	2	
28000400	PERIMETER EROSION BARRIER	FOOT	2,171	2,171	
28100107	STONE RIPRAP, CLASS A4	SQ YD	95		95
28100109	STONE RIPRAP, CLASS A5	SQ YD	14	14	
28100209	STONE RIPRAP, CLASS A5	TON	2,820		2,820
28100807	STONE DUMPED RIPRAP, CLASS AH	TON	25		25
28200200	FILTER FABRIC	SQ YD	1,134	14	1,120
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	330	330	
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	638	638	
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	75	75	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	16	16	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	440	440	
40600982	HOT-MIX ASPHALT REMOVAL - BUTT JOINT	SQ YD	278	278	
40600990	TEMPORARY RAMP	SQ YD	30	30	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N50	TON	252	252	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	12	12	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	254		254
42001300	PROTECTIVE COAT	SQ YD	254		254
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	52		52
44000100	PAVEMENT REMOVAL	SQ YD	217	217	
44000700	APPROACH SLAB REMOVAL	SQ YD	240		240
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,692	1,692	
48101600	AGGREGATE SHOULDER, TYPE B 8"	SQ YD	145	145	
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	1,196	1,196	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	43		43
50105220	PIPE CULVERT REMOVAL	FOOT	58	58	

• DENOTES SPECIALTY ITEM
•• NON-PARTICIPATING

80% FED
20% STATE

ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	BRIDGE X081-2A
50200100	STRUCTURE EXCAVATION	CU YD	1,560		1,560
50300225	CONCRETE STRUCTURES	CU YD	18.1		18.1
50300255	CONCRETE SUPERSTRUCTURES	CU YD	306.0		306.0
50300280	BRIDGE DECK GROOVING	SQ YD	698		698
50300300	PROTECTIVE COAT	SQ YD	920		920
50401005	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 48 IN.	FOOT	1,220		1,220
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	69,260		69,260
50800515	BAR SPLICERS	EACH	718		718
51205200	TEMPORARY SHEET PILING	SQ FT	560		560
51500100	NAME PLATES	EACH	1		1
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24		24
52100530	ANCHOR BOLTS, 1 1/4"	EACH	36		36
52100540	ANCHOR BOLTS, 1 1/2"	EACH	16		16
54215547	METAL END SECTIONS 12"	EACH	2	2	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	100		100
60100945	PIPE DRAINS 12"	FOOT	62	62	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	164		164
60500060	REMOVING INLETS	EACH	2	2	
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	2	2	
60900515	CONCRETE THRUST BLOCKS	EACH	2	2	
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	800	800	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	1,080	1,080	
63500105	DELINEATORS	EACH	6	6	
66101150	HOT-MIX ASPHALT SHOULDER CURB	FOOT	24	24	
66500105	WOVEN WIRE FENCE 4'	FOOT	202	202	
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	202	202	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	2	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	12	12	

FILE NAME =	USER NAME = USER	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES IL 84 OVER IRISH HOLLOW CREEK, S.N. 043-0037	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - EF	REVISED -			308	(103C-IBRID)	JO DAVIESS	62	4
	PLDT SCALE = 50,0000' / IN.	CHECKED - RJS	REVISED -		SCALE: N.T.S.					
	PLDT DATE = 12/17/2008	DATE - 12/11/08	REVISED -		SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		CONTRACT NO. 64C03