

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN	I000-2A	Y007
			TOTAL QUANTITY	80% FED 20% STATE	80% FED 20% STATE (SN 101-1079)
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15		15
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,724	3,724	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	13,766	13,766	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,907	4,907	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	340		340
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	230		230
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	47	47	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20,250	20,250	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	250	250	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	48	48	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	124	124	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,503	1,503	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	124	124	
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	31	31	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	432.5		432.5
X0712400	TEMPORARY PAVEMENT	SQ YD	1,897	1,897	
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	1,897	1,897	
X6064201	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	3,742	3,742	
Z0005400	BREAKER-RUN CRUSHED STONE	TON	434		434
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1
Z0024476	FLEXIBLE DELINEATOR MAINTENANCE	EACH	5		5
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	171	171	

* SPECIALTY ITEM

△ REVISED 2/18/09

FILE NAME = ct\projects\p211406\dl1406ovr.dgn	USER NAME = polzinej	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 303	SECTION (40R)T	COUNTY WINNEBAGO	TOTAL SHEETS 67	SHEET NO. 6
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 64C65		
PLOT DATE = Wed Aug 20 13:19:38 2008		DATE -	REVISED -							