

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	TOTAL	80% Fed 20% Stat RDWY 1000	50% STATE 50% CITY RDWY 1000	100% CITY RDWY Y060	80% Fed 20% State MINOR STRUCTURE Y007
54001000	BOX CULVERT END SECTIONS	EACH	2				2
54011003	PRECAST CONCRETE BOX CULVERT 10' X 3'	FOOT	66				66
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	92				92
542D1063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	68				68
54215553	METAL END SECTIONS 18"	EACH	6				6
60255500	MANHOLES TO BE ADJUSTED	EACH	4	3		1	
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	21			21	
60265800	VALVE VAULTS TO BE ADJUSTED (SPECIAL)	EACH	3			3	
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	1050				1050
61100605	MISCELLANEOUS CONCRETE	CU YD	2				2
61101013	STORM SEWERS PROTECTED, CLASS A, 12"	FOOT	104				104
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	4				4
63200310	GUARDRAIL REMOVAL	FOOT	400				400
63500105	DELINEATORS	EACH	4				4
66411900	TEMPORARY FENCE	FOOT	378				378
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	15				15
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	3				3
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1				1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CALMO	6	6			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5				5
67100100	MOBILIZATION	L SUM	1	1			
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1				1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			
70106700	TEMPORARY RUMBLE STRIP	EACH	6				6
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			

\*SPECIALTY ITEMS

FILE NAME =	USER NAME = dossdd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 73</b>	F.A.P. RTE. 654	SECTION *	COUNTY STEPHENSON	TOTAL SHEETS 89	SHEET NO. 7
cd:\pw\work\PW\DOT\DOSSDD\dms33571\d02967crr.dgn		DRAWN -	REVISED -							
	PLOT SCALE = 52.9412' / IN.	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.
	PLOT DATE = Wed Sep 24 07:38:28 2008	DATE -	REVISED -							ILLINOIS FED. AID PROJECT CONTRACT NO. 64C91