

# SUMMARY OF QUANTITIES

| CODE NUMBER     | ITEM   | UNITS | TOTAL  | 80% Fed<br>20% State<br>RDWY<br>1000 | 50% STATE<br>50% CITY<br>RDWY<br>1000 | 100% CITY<br>RDWY<br>Y060 | 80% Fed<br>20% State<br>MINOR<br>STRUCTURE<br>Y007 |
|-----------------|--|-------|--------|--------------------------------------|---------------------------------------|---------------------------|--|
| 70100500        | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326                      | L SUM | 1      | 1                                    |                                       |                           |  |
| <b>70300520</b> | <b>PAVEMENT MARKING TAPE, TYPE III 4"</b>                            | FOOT  | 1,820  |                                      |                                       |                           | 1,820  |
| 70100600        | TRAFFIC CONTROL AND PROTECTION, STANDARD 701336                      | L SUM | 1      | 1                                    |                                       |                           |  |
| <b>70300570</b> | <b>PAVEMENT MARKING TAPE, TYPE III 24"</b>                           | FOOT  | 48     |                                      |                                       |                           | 48   |
| 70101800        | TRAFFIC CONTROL AND PROTECTION, (SPECIAL)                            | L SUM | 1      |                                      |                                       |                           | 1  |
| 70300100        | SHORT-TERM PAVEMENT MARKING  | FOOT  | 17195  | 17195                                |                                       |                           |  |
| <b>70400100</b> | <b>TEMPORARY CONCRETE BARRIER</b>                                    | FOOT  | 325    |                                      |                                       |                           | 325  |
| 70301000        | WORK ZONE PAVEMENT MARKING REMOVAL                                   | SQ FT | 2565   | 1911                                 |                                       |                           | 654  |
| <b>78300100</b> | <b>PAVEMENT MARKING REMOVAL</b>                                      | SQ FT | 221    |                                      |                                       |                           | 221  |
| * 78001110      | PAINT PAVEMENT MARKING - LINE 4"                                     | FOOT  | 362237 | 362237                               |                                       |                           |  |
| <b>70400200</b> | <b>RELOCATE TEMPORARY CONCRETE BARRIER</b>                           | FOOT  | 325    |                                      |                                       |                           | 325  |
| * 78100100      | RAISED REFLECTIVE PAVEMENT MARKER                                    | EACH  | 723    | 723                                  |                                       |                           |  |
| 78300200        | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL                            | EACH  | 653    | 653                                  |                                       |                           |  |
| XX001135        | PAVEMENT PATCHING SPECIAL  | SQ YD | 75.2   |                                      |                                       |                           | 75.2   |
| <b>X0712400</b> | <b>TEMPORARY PAVEMENT</b>  | SQ YD | 133    |                                      |                                       |                           | 133  |
| X0322121        | SHEET WATERPROOFING MEMBRANE SYSTEM                                  | SQ YD | 161    | 161                                  |                                       |                           |  |
| <b>X0919000</b> | <b>TEMPORARY PAVEMENT REMOVAL</b>                                    | SQ YD | 133    |                                      |                                       |                           | 133  |
| Z0005400        | BREAKER-RUN CRUSHED STONE  | TON   | 269    |                                      |                                       |                           | 269  |
| Z0013798        | CONSTRUCTION LAYOUT  | L SUM | 1      |                                      |                                       |                           | 1  |
| Z0017100        | DOWEL BARS   | EACH  | 80     |                                      |                                       |                           | 80   |
| Z0025500        | FURNISHING AND INSTALLING PROPERTY MARKERS                           | EACH  | 2      |                                      |                                       |                           | 2  |
| Z0028415        | GEOTECHNICAL REINFORCEMENT   | SQ YD | 494    | 494                                  |                                       |                           |  |
| <b>Z0030250</b> | <b>IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3</b> | EACH  | 2      |                                      |                                       |                           | 2  |
| Z0028700        | GRANULAR SUBGRADE REPLACEMENT  | CU YD | 82     | 82                                   |                                       |                           |  |
| <b>Z0030350</b> | <b>IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3</b>  | EACH  | 2      |                                      |                                       |                           | 2  |
| Z0040315        | PILOT CAR  | DAY   | 14     | 14                                   |                                       |                           |  |
| Z0055100        | RUMBLE RESURFACING   | SQ YD | 92     | 92                                   |                                       |                           |  |
| Z0075300        | TIE BARS   | EACH  | 32     |                                      |                                       |                           | 32   |

\*SPECIALTY ITEMS

|  |                    |            |           |   |              |   |              |                      |                       |                   |         |
|--|--------------------|------------|-----------|---|--------------|---|--------------|----------------------|-----------------------|-------------------|---------|
| FILE NAME =                                      | USER NAME = dosadd | DESIGNED - | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>IL 73</b> | F.A.P.<br>RTE.<br>654                         | SECTION<br>* | COUNTY<br>STEPHENSON | TOTAL<br>SHEETS<br>89 | SHEET<br>NO.<br>8 |         |
| cr:\pwork\pwork\pwork\pwork\dms33571\d829707.dgn |                    | DRAWN -    | REVISED - |   |              |   |              |                      |                       |                   |         |
| PLOT SCALE = 52.9412' / IN.                      |                    | CHECKED -  | REVISED - |   |              |   |              |                      |                       |                   |         |
| PLOT DATE = Wed Sep 24 07:39:06 2008             |                    | DATE -     | REVISED - |   |              |   |              |                      |                       |                   |         |
|  |                    |            |           |   |              | SCALE:  | SHEET NO.    | OF                   | SHEETS                | STA.              | TO STA. |
|  |                    |            |           |   |              | FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT |              |                      |                       |                   |         |
|  |                    |            |           |   |              | CONTRACT NO. 64C91                            |              |                      |                       |                   |         |