

PATCHING SCHEDULE

13FOOT LANE WIDTH

7FOOT LANE WIDTH FOR 1/2 LANE PATCH

STATION	REMARKS	LENGTH OF PATCH		AREA OF CLASS B PATCHES, 14"								HMA REMOVAL OVER PATCHES 7"		HMA REPLACEMENT OVER PATCHES, 7"	
		LT LANE (feet)	RT LANE (feet)	TYPE 1		TYPE 2		TYPE 3		TYPE 4		LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (tons)	RT LANE (tons)
				LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)				
2 + 20		30	50							43.3	72.2	44.6	73.5	17.50	28.82
3 + 95			70								101.1		102.4		40.15
4 + 89		6	6			8.7	8.7					10.0	10.0	3.91	3.91
5 + 35			6				8.7						10.0		3.91
5 + 80			6				8.7						10.0		3.91
6 + 25		6				8.7						10.0		3.91	
7 + 47		6	6			8.7	8.7					10.0	10.0	3.91	3.91
7 + 67			6				8.7						10.0		3.91
8 + 75			18								26.0		27.3		10.70
9 + 45			6				8.7						10.0		3.91
9 + 63			6				8.7						10.0		3.91
9 + 95			20								28.9		30.2		11.83
11 + 40			100								144.4		145.7		57.13
12 + 00		6				8.7						10.0		3.91	
18 + 15		6	6			8.7	8.7					10.0	10.0	3.91	3.91
18 + 44		6	6			8.7	8.7					10.0	10.0	3.91	3.91
18 + 74		6				8.7						10.0		3.91	
19 + 13			78								112.7		114.0		44.67
20 + 7		10	10			14.4	14.4					15.7	15.7	6.17	6.17
21 + 00		6	6			8.7	8.7					10.0	10.0	3.91	3.91
21 + 78		6	6			8.7	8.7					10.0	10.0	3.91	3.91
22 + 81		6	6			8.7	8.7					10.0	10.0	3.91	3.91
25 + 31			14						20.2				21.5		8.44
27 + 50			6				8.7						10.0		3.91
29 + 32		6	6			8.7	8.7					10.0	10.0	3.91	3.91
30 + 55		6	6			8.7	8.7					10.0	10.0	3.91	3.91
32 + 57			6				8.7						10.0		3.91
33 + 2		6	6			8.7	8.7					10.0	10.0	3.91	3.91
33 + 92		6	6			8.7	8.7					10.0	10.0	3.91	3.91
34 + 83			8				11.6						12.9		5.04
35 + 74		6	6			8.7	8.7					10.0	10.0	3.91	3.91
36 + 20		6				8.7						10.0		3.91	
37 + 60		6	6			8.7	8.7					10.0	10.0	3.91	3.91
38 + 95		6	6			8.7	8.7					10.0	10.0	3.91	3.91
40 + 95		6	6			8.7	8.7					10.0	10.0	3.91	3.91
41 + 43			30								43.3		44.6		17.50

FILE NAME =	USER NAME = dmsdd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 73				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
or:\pw_work\PWIDOT\DOSSDD\dms33571\d82977.cvr.dgn		DRAWN -	REVISED -						654	*	STEPHENSON	89	22
PLOT SCALE = 50,0000' / IN.		CHECKED -	REVISED -						CONTRACT NO. 64C91				
PLOT DATE = Wed Sep 24 07:49:09 2008		DATE -	REVISED -						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				