

PATCHING SCHEDULE

13FOOT LANE WIDTH

7FOOT LANE WIDTH FOR 1/2 LANE PATCH

STATION	REMARKS	LENGTH OF PATCH		AREA OF CLASS B PATCHES, 14"								HMA REMOVAL OVER PATCHES 7"		HMA REPLACEMENT OVER PATCHES, 7"	
				TYPE 1		TYPE 2		TYPE 3		TYPE 4					
		LT LANE (feet)	RT LANE (feet)	LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (tons)	RT LANE (tons)
500 + 37		6				8.7							10.0		3.91
504 + 45		6				8.7							10.0		3.91
510 + 96			25								36.1			37.4	14.67
511 + 60			8					11.6						12.9	5.04
511 + 86		6	6			8.7	8.7						10.0	10.0	3.91 3.91
513 + 75		6	6			8.7	8.7						10.0	10.0	3.91 3.91
514 + 77			6				8.7							10.0	3.91
516 + 42		25	25							36.1	36.1		37.4	37.4	14.67 14.67
530 + 25		6	6			8.7	8.7						10.0	10.0	3.91 3.91
532 + 24		25	25							36.1	36.1		37.4	37.4	14.67 14.67
539 + 20		6	15			8.7			21.7				10.0	23.0	3.91 9.00
539 + 73		6	6			8.7	8.7						10.0	10.0	3.91 3.91
541 + 13			6				8.7							10.0	3.91
547 + 24			20										28.9	30.2	11.83
547 + 86			10				14.4							15.7	6.17
548 + 75			100										144.4	145.7	57.13
557 + 50		20								28.9			30.2		11.83
558 + 49		15							21.7				23.0		9.00
561 + 36		6	6			8.7	8.7						10.0	10.0	3.91 3.91
561 + 87		6				8.7							10.0		3.91 0.00
562 + 2			50											73.5	28.82
562 + 50		25								36.1			37.4		14.67
563 + 23			6				8.7							10.0	3.91
563 + 78		6	6			8.7	8.7						10.0	10.0	3.91 3.91
564 + 59		6	6			8.7	8.7						10.0	10.0	3.91 3.91
565 + 39		6	6			8.7	8.7						10.0	10.0	3.91 3.91
565 + 88			6				8.7							10.0	3.91
567 + 49		6	6			8.7	8.7						10.0	10.0	3.91 3.91
568 + 48		6	6			8.7	8.7						10.0	10.0	3.91 3.91
568 + 85		6				8.7							10.0		3.91
569 + 95		6	6			8.7	8.7						10.0	10.0	3.91 3.91
570 + 80		28	6				8.7			40.4			41.7	10.0	16.36 3.91
571 + 64		8	8			11.6	11.6						12.9	12.9	5.04 5.04
573 + 48		6				8.7							10.0		3.91
574 + 69		45	25							65.0	36.1		66.3	37.4	25.99 14.67
577 + 87		26	26							37.6	37.6		38.9	38.9	15.23 15.23
Total						1422.8	1521.0	257.1	338.0	2277.9	3466.7	4225.6	5636.4	1656.4	2209.5
Expect to replace 5% +/- of total						71.1	76.1	25.7	33.8	113.9	173.3				
Grand Total						147.2		59.5		287.2		9861.9		3865.9	

FILE NAME =	USER NAME = dmsdd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 73	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pw_work\PWIDOT\DOSSDD\dms33571\082977.dgn	PLOT SCALE = 50.0000' / IN.	DRAWN -	REVISED -			654	*	STEPHENSON	89	28	
PLOT DATE = Wed Sep 24 07:51:58 2008	DATE -	CHECKED -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					
		DATE -	REVISED -			CONTRACT NO. 64C91					