

# SUMMARY OF QUANTITIES

CONTRACT NO. 64D24

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
88	*	**	64	4
STA.		TO STA.		
FED. AID PROJECT ILLINOIS		FED. ROAD DIST. NO.		
• BRIDGE DECK REPAIRS 2007-1 •• ROCK ISLAND & WHITESIDE				



PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	S.N. 081-0126		S.N. 081-0132		S.N. 098-0058		S.N. 098-0066	
				90% FEDERAL 10% STATE X2 31-2A 286TH ST	100% ROCK ISLAND COUNTY X2 31-2A 286TH ST	90% FEDERAL 10% STATE X2 31-2A 317TH ST	100% ROCK ISLAND COUNTY X2 31-2A 317TH ST	90% FEDERAL 10% STATE X2 31-2A WILMOT RD	100% FENTON TOWNSHIP X2 31-2A WILMOT RD	90% FEDERAL 10% STATE X2 31-2A LYNDON RD	100% WHITESIDE COUNTY X2 31-2A LYNDON RD
28100107	STONE RIPRAP, CLASS A4	SQ. YD.	380	96		115		98		71	
28200200	FILTER FABRIC	SQ. YD.	380	96		115		98		71	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	324	53	23	64	26	63	14	69	12
42001300	PROTECTIVE COAT	SQ. YD.	94			25		35		34	
44004250	PAVED SHOULDER REMOVAL	SQ. YD.	91			25		30		36	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ. YD.	2822	632	149	766	178	748	149		
44001114	HOT-MIX ASPHALT SURFACE REMOVAL (ASBESTOS)	SQ. YD.	951							827	124
48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SQ. YD.	93			24		35		34	
50102400	CONCRETE REMOVAL	CU. YD.	32.1	6.6		9.1		8.3		8.1	
50157300	PROTECTIVE SHIELD	SQ. YD.	1101	243		286		273		299	
50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	35.8	7.0		9.9		9.6		9.3	
50300300	PROTECTIVE COAT	SQ. YD.	84	16		21		24		23	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6740	1520		1690		1570		1960	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	34	8		8		8		10	
50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1							
50600700	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1			1					
50600800	CLEANING AND PAINTING STEEL BRIDGE NO. 3	L SUM	1					1			
50600900	CLEANING AND PAINTING STEEL BRIDGE NO. 4	L SUM	1							1	
50606401	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1							
50606402	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1			1					
50606403	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 3	L SUM	1					1			
50606404	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 4	L SUM	1							1	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5210	1,040		1,360		1,420		1,390	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	274	61		72		68		73	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	34	8		8		8		10	
52100520	ANCHOR BOLTS, 1"	EACH	136	32		32		32		40	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ. YD.	3520	622	147	755	175	737	147	816	121
60260100	INLETS TO BE ADJUSTED	EACH	12				4		4		4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	2		2		2		2	
67100100	MOBILIZATION	L SUM	1	0.25		0.25		0.25		0.25	
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	8	2		2		2		2	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.25		0.25		0.25		0.25	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.25		0.25		0.25		0.25	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.25		0.25		0.25		0.25	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1420	355		355		355		355	
70300520	PAVEMENT MARKING TAPE, TYPE III LINE 4"	FOOT	48664	12,136		12,176		12,168		12,184	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	16,221	4,045		4,059		4,056		4,061	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	486							486	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3366	948		968		964		486	

• DENOTES SPECIALTY ITEM

△ REVISED 2/18/09

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 BRIDGE REHABILITATION  
 OVER I-88  
 ROCK ISLAND AND  
 WHITESIDE COUNTIES  
**SUMMARY OF QUANTITIES**  
 SCALE: NTS  
 DATE 12/09/08  
 DRAWN BY EF  
 CHECKED BY RS