

F.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	*	IROQUOIS	16	3
STA.		TO STA.		
FED. ROAD DIST. NO. 8		ILLINOIS	FED. AID PROJECT	

*(123)RS-1 & (135)RS-2

SUMMARY OF QUANTITIES			80% FED.
CODE NO.	ITEM	UNIT	20% STATE
			I000 TOTAL QUANTITY
20400800	FURNISHED EXCAVATION	CU YD	52
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13,796
40600300	AGGREGATE (PRIME COAT)	TON	345
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	49
40600525	LEVELING BINDER (HAND METHOD), N50	TON	81
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	6652
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,485
40600990	TEMPORARY RAMP	SQ YD	247
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	14364
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	875
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	80,769
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	173
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,816
50102400	CONCRETE REMOVAL	CU YD	0.07
50800105	REINFORCEMENT BARS	POUND	23
54002020	EXPANSION BOLTS 3/4 INCH	EACH	14
54248510	CONCRETE COLLAR	CU YD	0.27
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16,672
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	122
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	114,528
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	13,453
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	78

SUMMARY OF QUANTITIES			80% FED.
CODE NO.	ITEM	UNIT	20% STATE
			I000 TOTAL QUANTITY
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,852
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	122
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,349
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	934
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	78
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	113,179
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	12,519
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	766
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	766
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1
X0325866	CENTERLINE RUMBLE STRIP	FOOT	4000
X0914100	PRECAST CONCRETE BOX CULVERT END SECTIONS 3' X 2'	EACH	1

* SPECIALTY ITEMS

200.../SCHEDULES.DGN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY