

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAU ROUTE 6757 (US ROUTE 150)			80% FED.	CONSTRUCTION TYPE CODE		
SUMMARY OF QUANTITIES			20% STATE	RWY	STR	STR
CODE NO.	ITEM	UNIT	URBAN TOTAL	M 1000	BRM X020-2A	M X081-2A
44000600	SIDEWALK REMOVAL	SQ FT	103	103		
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	998	998		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2330	2330		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	786	786		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1887	1887		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1		
50104650	SLOPE WALL REMOVAL	SQ YD	175	175		
50105210	REMOVE EXISTING CULVERTS	FOOT	5	5		
50105220	PIPE CULVERT REMOVAL	FOOT	617.5	617.5		
50200100	STRUCTURE EXCAVATION	CU YD	1160		710	450
50300225	CONCRETE STRUCTURES	CU YD	383.5		322.3	61.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	524.0		377.4	146.6
50300260	BRIDGE DECK GROOVING	SQ YD	645			645
50300280	CONCRETE ENCASMENT	CU YD	16.0		16.0	
50300300	PROTECTIVE COAT	SQ YD	794			794
50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	558			558
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	168547	37	134070	34440
50800515	BAR SPLICERS	EACH	543		224	319
50901125	STEEL RAILING (TEMPORARY)	FOOT	102		72	30

2 REVISED 2/17/09

FAU ROUTE 6757 (US ROUTE 150)			80% FED.	CONSTRUCTION TYPE CODE		
SUMMARY OF QUANTITIES			20% STATE	RWY	STR	STR
CODE NO.	ITEM	UNIT	URBAN TOTAL	M 1000	BRM X020-2A	M X081-2A
50901720	BICYCLE RAILING	FOOT	78			78
51200957	FURNISHING METAL SHELL PILES 12" x 0.250"	FOOT	1159			1159
51201600	FURNISHING STEEL PILES HP 12x53	FOOT	3015		3015	
51202305	DRIVING PILES	FOOT	4174		3015	1159
51203200	TEST PILE METAL SHELLS	EACH	2			2
51203600	TEST PILE STEEL HP 12x53	EACH	1		1	
51205200	TEMPORARY SHEET PILING	SQ FT	1428			1428
51500100	NAME PLATES	EACH	2		1	1
54001000	BOX CULVERT END SECTIONS	EACH	1	1		
54002020	EXPANSION BOLTS 3/4 INCH	EACH	8	8		
54010404	PRECAST CONCRETE BOX CULVERT 4' X 4'	FOOT	10.2	10.2		
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	192.5	192.5		
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	45	45		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1		
54215547	METAL END SECTIONS 12"	EACH	2	2		
54215553	METAL END SECTIONS 18"	EACH	2	2		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	5	5		
X0326228	STORM SEWERS, PVC. SDR 26, 18"	FOOT	103	103		
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	33	33		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	507		383	124
60100945	PIPE DRAINS 12"	FOOT	78	78		
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	586		432	154