TRAFFIC CONTROL

LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	TEMPORARY PAVEMENT MARKING (WHITE)	TEMPORARY PAVEMENT MARKING (YELLOW)	IMPACT ATTENUATOR TEMPORARY (FULLY REDIRECTIVE, NARROW), TL3	IMPACT ATTENUATOR, RELOCATE (FULLY REDIRECTIVE), TL3	TRAFFIC CONTROL & PROTECTION STD. 701306	TRAFFIC CONTROL & PROTECTION STD. 701331 (SPECIAL)	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 (TEMP. PAV'T)	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT 0.00038 TON/ SQ. YD)
	FOOT				EACH		L SUM	EACH	TON	
US 150 S.N. 090-0038										
PRESTAGE									192	0.2
STAGE 1	483		1740	1690	2			1	703	0.6
STAGE 2	196	483	1840	1790	2	2		1		
US 150 S.N. 090-0040							1			
PRESTAGE									324	0.3
STAGE 1	514		1830	1830	2			1	488	0.5
STAGE 2	492	538	1830	1830	4	2		1		
TOTAL	1685	1021	7240	7140	10	4	1	4	1707	1.6

AGGREGATE SHOULDERS, TYPE B 6"

LOCATION		SQ. YD.
US 150 S.N. 090-0038		
47+35.00	47+59.41 LT	21.7
47+59.41	48+36.93 LT	43.1
49+20.78	50+34.40 LT	63.3
50+34.40	50+80.51 LT	41.0
50+80.51	50+92.14 LT	5.7
47+35.00	47+45.52 RT	5.8
47+82.53	48+11.74 RT	17.1
48+11.74	49+20.12 RT	60.2
50+05.34	50+99.38 RT	54.0
50+99.38	52+05.00 RT	93.8
N EAST LANE		
10+80.00	11+15.24 RT	7.8
11+37.59	11+41.11 RT	0.5
11+41.11	13+25.38 RT	41.0
10+80.00	12+37.13 LT	34.8
12+37.13	12+87.13 LT	27.8
12+87.13	13+29.31 LT	37.4
13+29.31	13+45.11 LT	9.9
CATHERINE STREET		
50+28.91	50+56.68 LT	8.8
US 150 S.N. 090-0040		
88+74.27	89+07.36 LT	12.6
90+07.14	90+44.50 LT	18.9
87+75.49	88+22.38 RT	22.8
88+22.38	89+15.83 RT	51.9
90+55.22	91+13.58 RT	32.4
91+13.58	91+66.45 RT	25.8
WEDGES		
S.N. 090-0038		12.5
N East Ln.		26.3
Catherine St.		2.0
S.N. 090-0040		8.8
	TOTAL	786

WORK ZONE

LOCATION	TRAFFIC CONTROL SURVEILLANCE	WORK ZONE PAVEMENT MARKING REMOVAL
	CAL DAY	SQ. FT.
US 150 S.N. 090-0038		
STAGE 1	15	651
STAGE 2		1110
US 150 S.N. 090-0040		
STAGE 1	15	685
STAGE 2		1103
TOTAL	30	3549

TERMINAL MARKER - DIRECT APPLIED

LOCATION	
STATION TO STATION	EACH
US 150 S.N. 090-0038	
47+59.41 LT	1
48+11.74 RT	1
50+34.41 LT	1
50+99.38 RT	1
US 150 S.N. 090-0040	
88+22.38 RT	1
88+67.50 LT	1
90+60.25 RT	1
TOTAL	7

BARRIER WALL MARKERS, TYPE B

LOCATION		EACH
S.N. 090-0040		
89+53.50	90+16.50 RT	2
89+44.67	90+07.67 LT	2
	TOTAL	4

TELESCOPING STEEL SIGN SUPPORT

S.N. 090-0038	
SIGN / INTERSECTION	FOOT
"DEAD END" S EAST LN / SHADOWAY DR	15
"STOP SIGN" N EAST LN / CATHERINE ST	15
"STOP SIGN" US 150 / CATHERINE ST	15
TOTAL	45

PIPE DRAINS 12"

LOCATION	FOOT
US 150 S.N. 090-0040	
NW CORNER	40
SW CORNER	38
TOTAL	78

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12

LOCATION	FOOT
S. EAST LN.	187
TOTAL	187

PIPE CULVERTS, CLASS A, TYPE 2 30"

LOCATION	FOOT
US 150 S.N. 090-0040	
90+50.0 TO 92+40.6 RT	192.5
TOTAL	192.5

2 REVISED 2/17/09

FILE NAME = E:\0102\Phase II\schedules.dgn	USER NAME = Plotted by Administrator	DESIGNED - ST	REVISED - ___
		DRAWN - ST	REVISED - ___
	PLOT SCALE = 50.0000 ' / IN.	CHECKED - FL	REVISED - ___
	PLOT DATE = 2/3/2009	DATE - 12/2007	REVISED - ___

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
US 150 OVER LITTLE FARM CREEK

SCALE: N/A | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6757	(105B) BR-2, (105B) BR-3	TAZEWELL	13	133
		CONTRACT NO. 68086		

FED. ROAD DIST. NO. _ | ILLINOIS | FED. AID PROJECT