HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

LOCATION	SQ. YD.
US 150 S.N. 090-0038	
47+35.00 TO 47+65.00	93.3
51+75.00 TO 52+05.00	94.8
N EAST LANE	
10+50.00 TO 10+80.00	62.4
CATHERINE STREET	
51+50.00 TO 51+80.00	75.1
US 150 S.N. 090-0040	
87+61.06 TO 87+91.06	96.1
91+94.00 TO 92+24.00	94.6
TOTAL	517

STRIP REFLECTIVE CRACK CONTROL TREATMENT

LOCATION	FOOT
US 150 S.N. 090-0038	
47+35.00 TO 52+05.00	940
N EAST LANE	
10+50.00 TO 13+46.36	296
CATHERINE STREET	
50+12.01 TO 51+80.00	168
US 150 S.N. 090-0040	
87+61.06 TO 92+24.00	926
TOTAL	2330

BOX CULVERT END SECTIONS

LOCATION	EACH
US 150 S.N. 090-0040	
92+45.49 RT	1
TOTAL	1

CONSTRUCTING TEST STRIP

LOCATION	EACH
US 150 S.N. 090-0038	1
US 150 S.N. 090-0040	1
TOTAL	2

STONE RIP RAP, CLASS A5

LOCATION	SQ. YD.
US 150 S.N. 090-0040	
90+29.20 90+49.93 RT	81
TOTAL	81

CLASS SI CONCRETE (OUTLET)

LOCATION	CU. YD.
US 150 S.N. 090-0040	
CULVERT EXTENSION COLLAR	0.9
TOTAL	0.9

PIPE CULVERTS, CLASS D, TYPE 1 18"

LOCATION	FOOT
US 150 S.N. 090-0040	
92+45.80 TO 92+90.29 RT	45
TOTAL	45

EXPANSION BOLTS 3/4 INCH

LOCATION	EACH
US 150 S.N. 090-0040	
CULVERT EXTENSION COLLAR	8
TOTAL	8

HOT-MIX ASPHALT SURFACE REMOVAL - VARIABLE DEPTH

LOCATION	SQ. YD.
US 150 S.N. 090-0038	
47+65.00 TO 48+50.78	276.4
49+91.13 TO 51+75.00	592.5
US 150 S.N. 090-0040	
87+91.06 TO 89+16.98	400.1
90+44.19 TO 91+94.00	479.6
Catherine St.	
51+10.00 TO 51+50.00	97.8
TOTAL	1847

FILTER FABRIC

LOCATION	SQ. YD.
US 150 S.N. 090-0040	
90+29.20 90+49.93 RT	81
TOTAL	81

MANHOLES, SPECIAL

S.N. 090-0040	EACH
92+40.55 33.75' RT	1
TOTAL	1

REMOVING MANHOLES

S.N. 090-0040	EACH
92+40.55 33.75' RT	1
TOTAL	1

PRECAST CONCRETE BOX CULVERT 4' X 4'

LOCATION	FOOT
US 150 S.N. 090-0040	
92+40.55 TO 92+46.36 RT	10.2
TOTAL	10.2

AGGREGATE FOR TEMPORARY ACCESS

LOCATION	TON
US 150 S.N. 090-0038	90
US 150 S.N. 090-0040	90
TOTAL	180

AGGREGATE FOR DRIVEWAY MAINTENANCE

LOCATION	TON
US 150 S.N. 090-0038	30
US 150 S.N. 090-0040	30
TOTAL	60

AGGREGATE SURFACE COURSE, TYPE B

LOCATION	TON
N EAST LANE	
11+40.00 RT	6.9
CATHERINE STREET	
50+99.34 LT	6.9
TOTAL	13.8

INLETS TYPE B, TYPE 37 GRATE

LOCATION	EACH
N EAST LANE	
12+03.06 16.80' LT	1
TOTAL	1

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"

S.N. 090-0040	EACH
90+50.00 44.50' RT	1
TOTAL	1

2 REVISED 2/17/09