

URBAN

← F →

HSIP

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY			MEDIAN
				J000-2A FED/STATE 80/20	MULTI-USE PATHWAY SFTY-1B FED/STATE/CITY 80/10/10	YO60 CITY 100%	J000-2A FED/STATE 90/10
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	37	37			
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	735	735			
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	1.67	1.67			
40600300	AGGREGATE (PRIME COAT)	TON	9.6	9.6			
40600525	LEVELING BINDER (HAND METHOD), N50	TON	30	30			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1801	1801			
40600990	TEMPORARY RAMP	SQ YD	861	861			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	145	145			
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	124	124			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	596	596			
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	44911	36885			8026
42001300	PROTECTIVE COAT	SQ YD	44911	36885			8026
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	559	559			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	3490	3490			
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	46237		46237		
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	433				433
42400420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SQ FT	5475		5475		
42400440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	2240		2240		
42400800	DETECTABLE WARNINGS	SQ FT	1058		722		336
48101200	AGGREGATE SHOULDERS, TYPE B	TON	23	23			
50105220	PIPE CULVERT REMOVAL	FOOT	483	483			
50800105	REINFORCEMENT BARS	POUND	227	227			

FILE NAME = sht-500.dgn	USER NAME = crespole	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 7 OF 434 SHEETS STA. TO STA.

F.A.P. RTE. 399	SECTION 36R-8	COUNTY Tazewell	TOTAL SHEETS 434	SHEET NO. 7
CONTRACT NO. 68258			ILLINOIS FED. AID PROJECT	