

URBAN

← F →

HSIP

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY			MEDIAN
				JO00-2A FED/STATE 80/20	MULTI-USE PATHWAY SFTY-1B FED/STATE/CITY 80/10/10	YO60 CITY 100%	JO00-2A FED/STATE 90/10
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2			
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1			
54215550	METAL END SECTIONS 15"	EACH	4	4			
54215985	REINFORCED CONCRETE PIPE ELBOW 30"	EACH	1	1			
54248510	CONCRETE COLLAR	CU YD	3.8	3.8			
55100500	STORM SEWER REMOVAL 12"	FOOT	1586	1586			
55100900	STORM SEWER REMOVAL 18"	FOOT	83	83			
55101100	STORM SEWER REMOVAL 21"	FOOT	230	230			
55101200	STORM SEWER REMOVAL 24"	FOOT	358	358			
55101300	STORM SEWER REMOVAL 27"	FOOT	102	102			
55101400	STORM SEWER REMOVAL 30"	FOOT	115	115			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	6				6
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	1			1
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1			
60224005	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 8 GRATE	EACH	1				1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	6	6			
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60241800	INLETS, TYPE G-1	EACH	22	22			
60241900	INLETS, TYPE G-1, SPECIAL	EACH	31	31			
60242400	INLETS, SPECIAL	EACH	3	3			
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2			

FILE NAME = sht-S00.dgn	USER NAME = crespole	DESIGNED -	REVISED -
		DRAWN -	REVISED -
PLDT SCALE = 48.0000' / IN.	CHECKED -	REVISED -	REVISED -
PLDT DATE = 12/11/2008	DATE -	REVISED -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 8 OF 434 SHEETS STA. TO STA.

F.A.P. RTE. 399	SECTION 36R-8	COUNTY Tazewell	TOTAL SHEETS 434	SHEET NO. 8
CONTRACT NO. 68258				
ILLINOIS FED. AID PROJECT				