

SCHEDULE OF QUANTITIES

(FOR INFORMATION ONLY)

COMBINATION CURB AND GUTTER REMOVAL	
LOCATION	LENGTH
STATION TO STATION	FEET
STA 140+27.95 TO STA 147+74.77	1497.5
LT STA.143+56.44 TO LT STA.148+12.08	478.3
RT STA.144+42.60 TO RT STA.147+83.82	369.2
RT STA.148+06.71 TO RT STA.157+22.63	960.6
LT STA.148+51.99 TO LT STA.152+69.87	490.3
STA 148+58 TO STA 152+41.62	764.7
STA.152+90.14 TO STA.156+84.18	777.3
LT STA.152+98.68 TO LT STA.156+86.12	424.2
LT STA.157+23.53 TO LT STA.160+13.20	350.0
RT STA.157+51.13 TO RT STA.164+41.86	776.7
STA.157+61.72 TO STA.159+97.30	477.9
LT STA.160+51.84 TO LT STA.163+79.27	381.7
STA.160+72.32 TO STA.164+04.32	668.5
LT STA.164+15.15 TO LT STA.167+16.49	345.7
STA.164+56.54 TO STA.167+16.50	530.1
RT STA.164+75.64 TO RT STA.167+30.58	356.8
LT STA.167+45.52 TO LT STA.170+38.00	326.4
RT STA.167+65.98 TO RT STA.170+21.48	301.2
STA.167+68.50 TO STA.170+08.63	486.0
RT STA.170+62.41 TO RT STA.172+21.27	213.2
LT STA.170+68.25 TO LT STA.177+09.57	672.8
STA.170+80.10 TO STA.172+35.36	314.9
RT STA.172+59.88 TO RT STA.175+65.37	371.8
STA.172+62.62 TO STA.175+71.81	624.6
RT STA.176+02.29 TO RT STA.179+11.04	348.8
STA.177+33.45 TO STA.179+25.56	397.9
STA.176+27.57 TO STA.177+02.39	156.8
LT STA.177+42.42 TO LT STA.180+89.13	387.1
RT STA.179+47.30 TO RT STA.182+64.71	388.1
STA.179+57.19 TO STA.180+73.36	239.5
LT STA.181+23.79 TO LT STA.184+15.75	318.5
STA.181+27.43 TO STA.182+68.89	294.8
RT STA.182+93.38 TO RT STA.186+20.20	413.1
STA.183+24.36 TO STA.184+12.01	183.2
STA.184+46.17 TO STA.186+29.74	380.3
LT STA.184+55.33 TO LT STA.187+81.05	350.4
STA.186+61.18 TO STA.187+55.27	192.2
RT STA.186+61.18 TO RT STA.189+56.16	350.0
LT STA.188+13.52 TO LT STA.192+91.71	534.0
STA.188+14.71 TO STA.192+74.79	930.0
RT STA.189+85.29 TO RT STA.192+54.59	351.8
LT STA.193+06.97 TO LT STA.193+28.62	93.1
RT STA.193+07.97 TO RT STA.195+02.91	402.3
LT STA.193+55.67 TO LT STA.196+36.98	313.3
TOTAL	19985.6

DRIVEWAY PAVEMENT REMOVAL	
LOCATION	AREA
STATION TO STATION	SQ YD
IL 8	
RT STA.145+87.40 TO RT STA.146+09.07	16.6
LT STA.146+19.99 TO LT STA.146+58.05	84.7
RT STA.146+70.88 TO RT STA.147+18.05	47.2
LT STA.146+73.65 TO LT STA.147+25.39	157.0
RT STA.149+35.37 TO RT STA.149+77.57	60.6
RT STA.150+13.81 TO RT STA.150+40.82	48.9
LT STA.150+57.83 TO LT STA.150+92.97	46.9
RT STA.150+96.09 TO RT STA.151+16.62	47.0
LT STA.151+07.47 TO LT STA.151+62.84	138.1
RT STA.151+83.33 TO RT STA.152+27.60	44.2
RT STA.152+47.46 TO RT STA.154+11.34	241.0
LT STA.153+87.21 TO LT STA.154+32.82	20.6
RT STA.154+49.38 TO RT STA.154+89.41	77.8
LT STA.155+29.65 TO LT STA.155+74.82	55.1
RT STA.155+83.27 TO RT STA.156+26.53	77.8
LT STA.157+93.06 TO LT STA.158+36.38	91.7
RT STA.158+50.33 TO RT STA.158+79.29	11.8
RT STA.158+85.83 TO RT STA.159+32.69	65.8
LT STA.158+85.52 TO LT STA.159+34.94	145.0
RT STA.160+16.22 TO RT STA.160+59.92	67.0
LT STA.162+43.98 TO LT STA.162+65.85	21.8
RT STA.162+78.83 TO RT STA.163+22.47	65.5
RT STA.163+40.66 TO RT STA.163+79.80	61.9
LT STA.165+37.79 TO LT STA.165+60.23	13.3
LT STA.165+82.15 TO LT STA.166+04.34	11.1
LT STA.166+15.95 TO LT STA.166+37.46	11.1
RT STA.167+98.71 TO RT STA.168+42.00	71.3
RT STA.168+80.82 TO RT STA.169+25.69	50.2
RT STA.169+51.68 TO RT STA.169+95.33	63.2
LT STA.171+42.25 TO LT STA.172+04.54	59.9
LT STA.173+19.13 TO LT STA.173+47.49	44.1
RT STA.174+16.74 TO RT STA.174+48.43	34.8
LT STA.174+43.49 TO LT STA.174+94.01	73.4
LT STA.175+74.84 TO LT STA.176+21.03	47.2
RT STA.177+16.74 TO RT STA.177+83.26	40.9
LT STA.178+33.18 TO LT STA.179+50.33	229.3
LT STA.180+04.86 TO LT STA.180+50.61	95.6
RT STA.180+32.84 TO RT STA.180+79.59	54.5
RT STA.181+87.40 TO RT STA.181+47.19	66.0
RT STA.181+91.51 TO RT STA.182+29.89	49.6
LT STA.182+69.87 TO LT STA.183+15.56	51.9
RT STA.183+44.73 TO RT STA.183+79.89	44.9
RT STA.184+21.28 TO RT STA.184+60.94	48.9
RT STA.184+83.93 TO RT STA.185+18.19	41.2
LT STA.186+30.96 TO LT STA.186+76.00	56.4
LT STA.187+03.74 TO LT STA.187+46.96	54.7
RT STA.187+59.42 TO RT STA.188+00.27	49.4
LT STA.189+57.53 TO LT STA.189+78.65	12.5
RT STA.190+35.18 TO RT STA.190+70.74	60.1
RT STA.191+15.73 TO RT STA.191+54.31	44.9
RT STA.191+86.60 TO RT STA.192+33.29	54.0
RT STA.193+38.15 TO RT STA.193+76.54	64.0
RT STA.196+97.99 TO RT STA.197+41.28	83.5
RT STA.197+84.86 TO RT STA.198+29.88	114.7
RT STA.198+43.74 TO RT STA.198+97.29	93.4
CARLSON AV.	
RT STA.10+54.15 TO RT STA.10+79.50	66.2
LT STA.10+50.69 TO LT STA.11+18.03	81.5
CHERRY LN.	
LT STA.9+52.42 TO LT STA.8+94.24	80.2
FLORIDA AV.	
LT STA.10+58.24 TO LT STA.10+95.27	34.5
RT STA.10+73.25 TO RT STA.11+17.99	42.5
SHERWOOD PARK	
LT STA.10+87.88 TO LT STA.10+46.03	68.1
ARGO ST.	
LT STA.10+54.69 TO LT STA.10+97.08	59.3
TOTAL	4016.3

MEDIAN SURFACE REMOVAL	
LOCATION	AREA
STATION TO STATION	SQ FT
STA.140+30.61 TO STA.142+43.66	877.5
STA.146+00 TO STA.147+71.90	948.7
STA.148+60.14 TO STA.152+37.48	2168.4
STA.155+04.07 TO STA.156+85.33	922.5
STA.157+86.63 TO STA.159+95.52	717.6
STA.160+91.97 TO STA.162+08.30	653.3
STA.165+82.62 TO STA.167+14.55	677.0
STA.167+97.62 TO STA.170+05.59	557.8
STA.170+97.47 TO STA.172+33.90	611.3
STA.176+29.29 TO STA.176+71.76	157.0
STA.176+75.67 TO STA.177+00.65	112.8
STA.179+58.37 TO STA.179+91.73	144.6
STA.179+95.99 TO STA.180+70.97	320.6
STA.183+44.72 TO STA.184+09.71	297.1
STA.186+65.32 TO STA.186+87.93	91.3
STA.186+91.40 TO STA.187+55.27	273.6
STA.188+36.05 TO STA.192+50.33	1622.7
TOTAL	11153.8

RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL	
LOCATION	EACH
STATION TO STATION	
E.B. STA.135+50 TO E.B. STA.196+84.92	87.0
W.B. STA.135+50 TO W.B. STA.196+84.93	80.0
TOTAL	167.0

PAVED DITCH REMOVAL	
LOCATION	LENGTH
STATION TO STATION	FEET
RT STA.142+29.38 TO RT STA.144+42.89	211.3
TOTAL	211.3

MEDIAN REMOVAL	
LOCATION	AREA
STATION TO STATION	SQ FT
STA.137+46.88 TO STA.139+56.75	1611.5
STA.152+91.84 TO STA.153+00.58	43.4
STA.157+64.06 TO STA.157+81.17	19.5
STA.160+75.84 TO STA.160+85.43	15.7
STA.163+90.44 TO STA.164+01.80	57.6
STA.164+58.21 TO STA.164+69.50	57.7
STA.167+70.36 TO STA.167+92.30	59.9
STA.170+83.31 TO STA.170+92.83	21.5
STA.172+65.04 TO STA.172+76.50	55.4
STA.175+59.37 TO STA.175+70.19	54.3
STA.177+35.11 TO STA.177+46.00	56.8
STA.179+12.26 TO STA.179+23.86	57.0
STA.181+29.05 TO STA.181+41.38	63.9
STA.182+57.57 TO STA.182+66.39	43.6
STA.183+25.65 TO STA.183+40.63	28.9
STA.184+47.80 TO STA.184+59.66	62.1
STA.186+19.80 TO STA.186+28.24	45.0
STA.188+14.48 TO STA.188+28.30	29.3
STA.192+56.18 TO STA.192+73.12	45.2
TOTAL	2428.3

PARKING BLOCK REMOVAL	
LOCATION	EACH
STATION TO STATION	
STA.135+50 TO STA.196+84.92	241
TOTAL	241

PAVED SHOULDER REMOVAL	
LOCATION	AREA
STATION TO STATION	SQ YD
RT STA.135+50.13 TO RT STA.139+20.04	78.9
RT STA.140+49.99 TO RT STA.144+53.43	175.3
LT STA.134+50.48 TO LT STA.145+44.75	701.4
TOTAL	955.6

PAVEMENT REMOVAL	
LOCATION	AREA
STATION TO STATION	SQ YD
IL 8	
STA.135+50 TO STA.194+60.00	36806.1
EXPO DR	
STA.139+92.97 TO STA.139+74.43	317.0
CHERRY LN	
STA.09+14.13 TO STA.09+64.93	217.7
HOLLY DR.	
STA.10+37.73 TO STA.10+77.51	156.2
STAHL AV.	
STA.10+38.71 TO STA.10+72.65	170.8
THEODORE ST.	
STA.9+24.78 TO STA.9+64.16	192.2
CRESTLAWN DR.	
STA.10+35.40 TO STA.10+89.40	277.8
BERRY ST.	
STA.10+37.88 TO STA.10+66.74	150.0
ALBERT ST.	
STA.9+14.11 TO STA.9+57.47	215.4
CARLSON AV.	
STA.10+36.51 TO STA.10+85.09	196.6
ESSER ST.	
STA.9+33.50 TO STA.9+61.77	141.7
MASON AV.	
STA.10+36.85 TO STA.10+71.48	158.8
LOREN ST.	
STA.9+29.59 TO STA.9+65.23	155.1
JAMES AV.	
STA.10+36.65 TO STA.10+73.79	169.8
DORIS ST.	
STA.9+25.41 TO STA.9+62.20	177.8
MARY ST.	
STA.9+25.65 TO STA.9+62.55	173.6
FLORIDA AV.	
STA.10+35.42 TO STA.10+71.14	164.0
BESS ST.	
STA.9+21.50 TO STA.9+62.38	175.2
MASSACHUTES AV.	
STA.10+35.47 TO STA.10+64.82	132.3
LAKE ST.	
STA.9+35.47 TO STA.14+17.20	165.3
SHERWOOD PARK RD.	
STA.10+39.42 TO STA.10+70.05	129.3
QUAIL TRAIL	
STA.9+22.67 TO STA.9+62.06	156.7
OAKDALE RD.	
STA.10+37.04 TO STA.10+83.18	103.9
MEADOW LN.	
STA.9+23.77 TO STA.9+60.59	161.4
NORTH BRIARGATE ST	
SOUTH BRIARGATE ST	
STA.9+33.55 TO STA.9+64.93	164.3
TOTAL	41373.1

SIDEWALK REMOVAL	
LOCATION	SQ FT
STATION TO STATION	
RT STA 155+28 - 155+76	182.4
TOTAL	182.4

FILE NAME = schedule.dgn	USER NAME = crespole	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

F.A.P. RTE. 399	SECTION 36 R-8	COUNTY TAZEWELL	TOTAL SHEETS 429	SHEET NO. 20
CONTRACT NO. 68258				

SCALE: SHEET NO. OF SHEETS STA. TO STA.

FED. ROAD DIST. NO. 4 (ILLINOIS) FED. AID PROJECT