

LOCATION OF WORK:

FAI 74  
RURAL  
MCLEAN COUNTY  
STA 1463+28.89 TO STA 297+86.57 (RAMP B)  
90% FEDERAL  
10% STATE  
SFTY-3J

FAI 74  
RURAL  
MCLEAN COUNTY  
STA 1463+28.89 TO STA 297+86.57 (RAMP B)  
90% FEDERAL  
10% STATE  
SFTY-3N

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY		
20200100	EARTH EXCAVATION	CU YD	122.0	0.0	122.0
20400800	FURNISHED EXCAVATION	CU YD	4,924.0	368.0	4556.0
* 25000210	SEEDING, CLASS 2A	ACRE	5.5	0.7	4.8
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	490.0	58.0	432.0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	490.0	58.0	432.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	490.0	58.0	432.0
* 25100115	MULCH, METHOD 2	ACRE	5.5	0.7	4.8
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	550.0	70.0	480.0
28000300	TEMPORARY DITCH CHECKS	EACH	35.0	0.0	35.0
28000500	INLET AND PIPE PROTECTION	EACH	4.0	0.0	4.0
50300225	CONCRETE STRUCTURES	CU YD	100.0	100.0	0.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9,480.0	9480.0	0.0
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	425.0	0.0	425.0
54215550	METAL END SECTIONS 15"	EACH	2.0	0.0	2.0
54246205	INLET BOX, STANDARD 542526	EACH	1.0	0.0	1.0
54248510	CONCRETE COLLAR	CU YD	0.5	0.0	0.5
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	61.0	0.0	61.0
60107600	PIPE UNDERDRAINS 4"	FOOT	60.0	0.0	60.0
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	1.0	0.0	1.0
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	9,512.5	9512.5	0.0
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	14.0	14.0	0.0
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	12.0	12.0	0.0
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	14.0	14.0	0.0

\* SPECIALTY ITEM

FILE NAME : c:\pwork\pwork\IDOT\CEARLOCK\JD\0101465\570744-shr-500.dgn	USER NAME : cearlockjd	DESIGNED - DRAWN -	REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I. RTE. 74	SECTION DSSAFETY-1	COUNTY McLean	TOTAL SHEETS 80	SHEET NO. 5
PLOT SCALE : 40.0000 "/>													