

PAVEMENT MARKING

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|-----------------------|---------------------------------|--------------|-----------|
| 809 | (133,134)RS-4,135RS-5 | ST. CLAIR, MONROE | 252 | 5 |
| STA. _____ | | TO STA. _____ | | |
| FED. ROAD DIST. NO. _____ | | ILLINOIS FED. AID PROJECT _____ | | |

| LOCATION | | | THERMOPLASTIC PAVEMENT MARKING | | | | | | | | | | RAISED REFLECTIVE PAVEMENT MARKER CRYSTAL | RAISED REFLECTIVE PAVEMENT MARKER AMBER | COMMENTS |
|----------------------|----|-----------|-----------------------------------|----------------------|-----------------------------------|-------------------------------|--------------------------------------|----------------------|-----------------------|----------------------|-------------------|----------------|---|---|----------|
| | | | 4" | | | | 8" | 12" | | 24" | LETTERS & SYMBOLS | | | | |
| STATION | TO | STATION | SOLID WHITE EDGE & LANE LINE FOOT | WHITE SKIP-DASH FOOT | SKIP-DASH YELLOW CENTER LINE FOOT | SOLID YELLOW CENTER LINE FOOT | SOLID DOUBLE YELLOW CENTER LINE FOOT | WHITE DIAGONALS FOOT | YELLOW DIAGONALS FOOT | WHITE DIAGONALS FOOT | | STOP BARS FOOT | SQ FT | EACH | EACH |
| IL 158 | | | | | | | | | | | | | | | |
| 141+67 | TO | 144+75 | 616 | | 77 | | 616 | | | | | | | 4 | |
| 144+75 | TO | 156+14 | 2278 | | 285 | 1139 | | | | | | | | 28 | |
| 156+14 | TO | 169+57 | 2476 | | | 1343 | 2686 | | | | | | | 17 | |
| 169+57 | TO | 177+57 | 1570 | 41 | | 1534 | 3356 | | 118 | | | 31.2 | 4 | 55 | |
| 177+57 | TO | 183+31 | 1057 | | | | 2226 | | 114 | | | | | | |
| 183+31 | TO | 191+99 | 1737 | | | | 1738 | | | | | | | 11 | |
| 191+99 | TO | 202+52 | 2105 | | 231 | 921 | 264 | | | | | | | 14 | |
| 202+52 | TO | 213+00 | 2097 | | 263 | 1049 | | | | | | | | 13 | |
| 213+00 | TO | 228+00 | 3000 | | | | 3002 | | | | | | | 18 | |
| 228+00 | TO | 240+85 | 2571 | | | | 2572 | | | | | | | 16 | |
| 240+85 | TO | 249+04 | 1574 | | | | 2872 | | 125 | | | 31.2 | 4 | 33 | |
| 249+04 | TO | 257+45 | 1583 | | | | 2872 | | 125 | | | 31.2 | 4 | 30 | |
| 257+45 | TO | 271+88 | 2887 | | | | 2888 | | | | | | | 19 | |
| 271+88 | TO | 279+22 | 1711 | 104 | | | 2760 | | 187 | | | 31.2 | 9 | 35 | |
| 279+22 | TO | 285+95 | 1423 | | | | 2204 | | 94 | | | 31.2 | 5 | 29 | |
| 285+95 | TO | 291+95 | 1100 | | | | 1200 | | | | | | | 8 | |
| 291+95 | TO | 302+00 | 2010 | | 252 | | | | | | | | | 12 | |
| 302+00 | TO | 316+00 | 2750 | | 350 | | | | | | | | | 18 | |
| 316+00 | TO | 329+00 | 2601 | | 325 | | | | | | | | | 17 | |
| 329+00 | TO | 334+00 | 1000 | | 125 | 500 | | | | | | | | 6 | |
| 334+00 | TO | 349+00 | 3000 | | | | 3000 | | | | | | | 18 | |
| 349+00 | TO | 361+00 | 2400 | | 300 | 1200 | | | | | | | | 15 | |
| 361+00 | TO | 367+25.70 | 1172 | | 157 | | | | | | | | | 8 | |
| Columbia Quarry Road | | | | | | | | | | | | | | | |
| | | | 516 | | | | 365 | 113 | | 314 | 30 | 31.2 | | | |
| Triple Lakes Rd. | | | | | | | | | | | | | | | |
| | | | 566 | | | | 445 | 91 | | 114 | 30 | | | | |
| Bohleysville Rd | | | | | | | | | | | | | | | |
| | | | 704 | | | | 577 | 56 | | 121 | 30 | | | | |
| Freeburg-Douglas Rd. | | | | | | | | | | | | | | | |
| | | | 1589 | 39 | | | 2346 | 257 | 104 | 376 | 48 | 78 | 4 | 24 | |
| SUB-TOTALS | | | 48093 | 184 | 2365 | 7686 | 37989 | 517 | 867 | 925 | | | 30 | 448 | |
| TOTAL | | | | | 96317 | | | 517 | 1792 | | 138 | 265.2 | | 478 | |

| SHORT TERM PAVEMENT MARKING & WORK ZONE REMOVAL | | | | |
|---|----|-----------|---------------------------------|---|
| LOCATION | | | SHORT-TERM PAV'T MARKING (FOOT) | WORK ZONE PAV'T MARKING REMOVAL (SQ FT) |
| IL 158 | | | | |
| STATION | TO | STATION | (FOOT) | (SQ FT) |
| 141+67 | TO | 144+75 | 528 | 176 |
| 144+75 | TO | 156+14 | 1488 | 496 |
| 156+14 | TO | 169+57 | 2608 | 869 |
| 169+57 | TO | 177+57 | 2608 | 869 |
| 177+57 | TO | 183+31 | 1328 | 443 |
| 183+31 | TO | 191+99 | 1392 | 464 |
| 191+99 | TO | 202+52 | 1408 | 469 |
| 202+52 | TO | 213+00 | 1376 | 459 |
| 213+00 | TO | 228+00 | 2400 | 800 |
| 228+00 | TO | 240+85 | 2064 | 688 |
| 240+85 | TO | 249+04 | 1776 | 592 |
| 249+04 | TO | 257+45 | 1792 | 598 |
| 257+45 | TO | 271+88 | 2320 | 774 |
| 271+88 | TO | 279+22 | 1840 | 614 |
| 279+22 | TO | 285+95 | 1456 | 485 |
| 285+95 | TO | 291+95 | 928 | 310 |
| 291+95 | TO | 302+00 | 912 | 304 |
| 302+00 | TO | 316+00 | 1248 | 416 |
| 316+00 | TO | 329+00 | 1184 | 395 |
| 329+00 | TO | 334+00 | 656 | 219 |
| 334+00 | TO | 349+00 | 2400 | 800 |
| 349+00 | TO | 361+00 | 1568 | 523 |
| 361+00 | TO | 367+25.70 | 544 | 182 |
| Columbia Quarry Road | | | 352 | 118 |
| Triple Lakes Rd. | | | 416 | 139 |
| Bohleysville Rd | | | 528 | 176 |
| Freeburg-Douglas Rd. | | | 1600 | 534 |
| TOTAL | | | 38720 | 12912 |

PLOT DATE = #DATE#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 REFERENCE = #REF#

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION PAVEMENT MARKING SCHEDULES FAP ROUTE 809 (IL 158) SECTION (133,134)RS-4,135RS-5 MONROE & ST. CLAIR COUNTIES |
|-----------|--------------|---|
| NAME | DATE | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| SCALE: | VERT. _____ | DRAWN BY _____ |
| DATE | HORIZ. _____ | CHECKED BY _____ |