CONTRACT NO. 76408

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-4,135RS-5	ST. CLAIR, MONROE	252	9
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SEEDING

LOCATION			TEMP. EROSION. CONTROL. SEEDING (lb)	SEEDING CL 2A (ac)	NITROGEN FERTILIZER NUTRIENT (lb)	PHOSPHORUS FERTILIZER NUTRIENT (lb)	POTASSIUM FERTILIZER NUTRIENT (lb)	MULCH METHOD 2 (ac)
STA	to	STA						
IL 158								
141+67	to	155+00	543.6	2.1	181.2	181.2	181.2	2.1
155+00	to	169+00	428.1	1.6	142.7	142.7	142.7	1.6
169+00	to	184+00	490.8	1.9	163.6	163.6	163.6	1.9
184+00	to	199+00	467.4	1.8	155.8	155.8	155.8	1.8
199+00	to	213+00	521.1	2.0	173.7	173.7	173.7	2.0
213+00	to	228+00	494.7	1.9	164.9	164.9	164.9	1.9
228+00	to	243+00	433.2	1.7	144.4	144.4	144.4	1.7
243+00	to	258+00	315.6	1.2	105.2	105.2	105.2	1.2
258+00	to	273+00	479.7	1.8	159.9	159.9	159.9	1.8
273+00	to	287+00	277.8	1.1	92.6	92.6	92.6	1.1
287+00	to	302+00	481.5	1.8	160.5	160.5	160.5	1.8
302+00	to	316+00	336.0	1.3	112.0	112.0	112.0	1.3
316+00	to	329+00	295.5	1.1	98.5	98.5	98.5	1.1
329+00	to	344+00	287.1	1.1	95.7	95.7	95.7	1.1
344+00	to	358+00	259.2	1.0	86.4	86.4	86.4	1.0
358+00	to	367+26	263.7	1.0	87.9	87.9	87.9	1.0
COL. QUARRY RD								
1+23	to	3+17	106.5	0.4	35.5	35.5	35.5	0.4
BOHLEYVILLE RD								
3+74	to	6+72	114.6	0.5	38.2	38.2	38.2	0.5
TRIPLE LAKES RD								
7+08	to	10+28	98.1	0.4	32.7	32.7	32.7	0.4
DOUGLAS RD								
5+25	to	12+34	261.0	1.0	87.0	87.0	87.0	1.0
		TOTAL =	6955	27	2318	2318	2318	27

RIGHT-OF-WAY AND PROPERTY CORNERS

LOCATION			
ALIGNMENT	STATION	OFFSET	EACH
IL 158	166+79.77	40.00' LT	1
IL 158	178+28.11	59.50' LT	1
IL 158	179+59.45	59.43' LT	1
IL 158	181+43.78	59.37' LT	1
IL 158	185+38.33	49.33' LT	1
TRIPLE LAKES ROAD	8+72.79	28.78' RT	1
TRIPLE LAKES ROAD	8+75.15	43.59' RT	1
IL 158	249+59.56	39.29' LT	1
IL 158	266+14.01	60.71' LT	1
IL 158	266+63.99	50.75' LT	1
IL 158	309+57.88	45.00' LT	1
IL 158	352+27.79	40.00' RT	1
IL 158	366+34.53	40.00' RT	1
		TOTAL	13

STONE DUMPED RIPRAP,
CLASS A3

LOCATION		
STA.	SIDE	(TONS)
147+50	LT	720
200+00	LT	830
204+85	LT	485
	TOTAL	2035

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SEEDING SCHEDULE

FAP ROUTE 809 (IL 158)
SECTION (133,134)RS-4,135RS-5
MONROE & ST. CLAIR COUNTIES

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = $DATE$
PLOT TIME = $TIME$
PLOT SCALE = $SCALE$
REFERENCE = REF