CONTRACT NO. 76408

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-4,135RS-5	ST. CLAIR, MONROE	252	11
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

ENTRANCE CULVERT SCHEDULE

LOCATION (STA)	COMMENTS	LT/RT	TYPE	SURFACE	PIPE CULVERTS, CLASS A TYPE 1 12" (FOOT)	PIPE CULVERTS, CLASS C TYPE 1 12" (FOOT)	15" (FOOT)	18" (FOOT)	30" (FOOT)	36" (FOOT)
161+84.86		LT	PE	AGG		34				
169+89.72		LT	PE	CONC		34				
180+82.54		RT	PE	AGG		35				
181+33.44		LT	PE	AGG		65				
185+85.52	DOUBLE DRIVEWAY	LT	PE	CONC	67					
189+20.74		LT	PE	AGG		24				
195+51.41		RT	FE	AGG		24				
201+90.52		LT	PE	AGG			42			
202+78.38		RT	PE	AGG		33				
206+63.61		LT	PE	AGG				29		
208+62.72	DOUBLE DRIVEWAY	LT	PE	AGG			45			
209+86.40		LT	PE	AGG			29			
212+45.00		RT	FE	AGG		43				
213+77.61		RT	PE	AGG		32				
216+34.5		LT	PE	AGG		53				
217+12.42		RT	PE	AGG		39				
218+29.62		LT	PE	AGG		29				
223+00.00		RT	FE	AGG		54				
224+30.66	LIMESTONE LN	LT	PE	CONC		60				
238+44.5		LT	FE	AGG	30					
239+00.00		LT	FE	AGG	34					
239+86.87		LT	PE	AGG		24				
4+62.41	BOHLEYSVILLE RD CL	RT	FE	AGG		28				
5+00.30	BOHLEYSVILLE RD CL	LT	FE	AGG		55				
251+38.83	FARMER'S INN	LT	CE	AGG		56				
254+55.3		RT	PE	AGG		25				
255+30.85		LT	CE	AGG		44				
262+49.36		RT	PE	AGG			27			
262+70.00		LT	FE	AGG		31				
266+40.61	PRAIRIE DR	LT	SR	BIT						47
273+00		LT	PE	AGG		33				
277+40.64		LT	PE	BIT		37				
7+17.36	DOUGLAS RD CL	RT	FE	AGG		28				
8+11.68	DOUGLAS RD CL	LT	FE	AGG		38				
11+63.72	DOUGLAS RD CL	RT	FE	AGG		46				
285+39.64		RT	PE	AGG		29				
288+03.24		LT	PE	AGG		33				
288+84.14		RT	PE	AGG			297			
291+09.87	ROENICKE RD	RT	SR	BIT						
297+26.93		RT	FE	AGG		28				
316+71		LT	FE	AGG						
316+71		RT	FE	AGG						
323+89		RT	FE	AGG			34			
326+33.64		LT	CE	CONC			60			
329+78		RT	PE	AGG		32				
329+88.67		LT	CE	CONC			52			

CONTINUED

ENTRANCE CULVERT SCHEDULE (CON'T)

LOCATION (STA)	COMMENTS	LT/RT	TYPE	SURFACE	PIPE CULVERTS, CLASS A TYPE 1 12" (FOOT)	PIPE CULVERTS, CLASS C TYPE 1 12" (FOOT)	15" (FOOT)	18" (FOOT)	30" (FOOT)	36" (FOOT)
330+93.88		RT	PE	BIT			32			
337+30.58		LT	CE	CONC		55				
337+98.00		LT	CE	CONC		52				
339+48.92		LT	PE	AGG		23				
340+55.93		LT	PE	AGG		23				
341+47.6		RT	FE	AGG		38				
341+74.65		LT	PE	AGG		23				
352+23		RT	FE	AGG		51				
354+30.2		RT	PE	BIT			52			
354+39		LT	FE	AGG						
356+60		LT	PE	BIT			41			
357+24.53		RT	CE	CONC			38			
358+71.87		RT	CE	CONC			49			
360+34.63		LT	PE	AGG			40			
361+76.25		RT	PE	AGG			38			
361+81.03		LT	PE	BIT			33			
364+65.70		LT	PE	AGG				32		
366+84.13	M&O STATION ST	RT	SR	CONC					81	
TOTAL =					131	1391	909	61	81	47

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ENTRANCE CULVERT SCHEDULE

FAP ROUTE 809 (IL 158)
SECTION (133,134)RS-4,135RS-5
MONROE & ST. CLAIR COUNTIES

SCALE: VERT. HORIZ. DRAWN BY
DATE CHECKED BY

PLOT DATE = $DATE$
FILE NAME = $FILE$
PLOT SCALE = $SCALE$
REFERENCE = REF