

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-4,135RS-5	ST. CLAIR, MONROE	252	12
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

## PAVEMENT SCHEDULE

LOCATION			406 AGGREGATE (PRIME COAT)	406 BITUMINOUS (PRIME COAT)	LEVELING BINDER (MACHINE METHOD)	SURFACE COURSE	HMA SHLDRS, 8"	HMA BASE COURSE, 11 3/4"	HMA BINDER COURSE	AGGREGATE SHOULDER, 6"	PROCESSING MODIFIED SOIL, 12"	LIME	PCC PAVEMENT 10"	SUB-BASE GRAN MAT'L, TYPE B 12"
STA	to	STA	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(SQ YD)
<i>IL 158</i>														
141+67	to	155+00	5.08	1.02	136.5	273.0	1187.0			1185.0				
155+00	to	169+00	5.86	1.17	157.2	314.4	1243.7			1244.4				
169+00	to	184+00	7.94	1.59	213.2	547.6	1378.6	1384.9		1333.3	1030	20		
184+00	to	199+00	5.74	1.15	154.1	308.1	1333.4			1333.3				
199+00	to	213+00	5.36	1.07	143.8	287.6	1244.4	529.2		1244.4				533.3
213+00	to	228+00	5.73	1.15	153.9	307.9	1338.7	672.8		1333.3				666.7
228+00	to	243+00	5.89	1.18	158.2	316.4	1331.8	886.3		1333.3	125	3		618.9
243+00	to	258+00	8.49	1.70	228.0	707.8	1555.9	2350.3		1333.3	1955	38		345.6
258+00	to	273+00	6.09	1.22	163.6	327.1	1333.7	757.9		1333.3	170	3		577.8
273+00	to	287+00	13.86	2.77	372.0	743.9	1796.2	2874.2		1244.4	2845	55		46.7
287+00	to	302+00	6.00	1.20	161.0	322.0	1333.3	16.9		1333.3				16.9
302+00	to	316+00	5.58	1.12	149.9	299.7	1241.5			1244.4				
316+00	to	329+00	5.19	1.04	139.4	278.7	1160.1			1155.6				
329+00	to	344+00	5.72	1.14	153.6	307.2	1341.6			1333.3				
344+00	to	358+00	5.36	1.07	143.8	287.6	1305.1			1244.4				
358+00	to	367+26	3.82	0.76	102.6	205.1	755.1			822.8				
<b>COL. QUARRY RD</b>														
1+23	to	3+17	1.69	0.34		121.2	121.1		727					1081.4
<b>BOHLEYVILLE RD</b>														
3+74	to	6+72	1.85	0.37		119.7	114.4		793					1179.7
<b>TRIPLE LAKES RD</b>														
7+08	to	10+28	1.67	0.33		132.2	232.0		2239					1068.7
<b>DOUGLAS RD</b>														
5+25	to	12+34					632.6						1545.0	1545.0
<b>*ADDITIONAL TONNAGE</b>						200								
<b>TOTAL =</b>			107	21	2931	6207	21980	9473	2239	20052	6125	119	1545	7680.7

\*ADDITIONAL TONNAGE - TO ACCOUNT FOR SURFACE IRREGULARITIES AND POTENTIAL DRAINAGE CORRECTIONS AS DIRECTED BY THE RESIDENT ENGINEER.

PLOT DATE = #DATE\*  
 FILE NAME = #FILE#\*  
 PLOT SCALE = #SCALE\*  
 REFERENCE = #REF#

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION <b>PAVEMENT SCHEDULE</b> FAP ROUTE 809 (IL 158) SECTION (133,134)RS-4,135RS-5 MONROE & ST. CLAIR COUNTIES
NAME	DATE	
		SCALE: VERT. _____ HORIZ. _____ DATE _____
DRAWN BY _____		CHECKED BY _____