

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-4,135RS-5	ST. CLAIR, MONROE	252	13
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

CONCRETE V-GUTTER SCHEDULE

LOCATION			LT/RT	CONCRETE GUTTER, TYPE A (FOOT)	CLASS SI CONCRETE (INLET) (CU YD)	CLASS SI CONCRETE (OUTLET) (CU YD)	CLASS SI CONCRETE (ENTRANCE) (CU YD)	OUTLET TYPE 1 FOR TYPE A GUTTER	
STA.	TO	STA.						(OUTLET) (CU YD)	GRATE TYPE A (EACH)
164+70	TO	165+24	LT			4.68			
165+24	TO	165+51	LT				2.81		
165+51	TO	166+60	LT	108.08					
166+60	TO	166+88	LT				5.41		
166+88	TO	166+95	LT		1.4*				
173+25	TO	173+80	RT			4.68			
173+80	TO	180+00	RT	610.94					
180+00	TO	180+12	RT		0.92				
237+67	TO	238+20	LT			4.68			
238+20	TO	238+31.3	LT	11.32					
238+31.3	TO	238+57.4	LT				2.69		
238+57.4	TO	238+87	LT	29.63					
238+87	TO	239+13	LT				2.69		
239+13	TO	239+74.8	LT	61.83					
239+74.8	TO	239+96.3	LT				2.16		
239+96.3	TO	241+50	LT	153.67					
241+50	TO	241+62	LT		0.92				
243+21	TO	243+76	RT			4.68			
243+76	TO	244+19	RT				4.56		
244+19	TO	247+00	RT	280.88					
247+00	TO	247+12	RT		0.92				
TRIPLE LAKES RD									
9+52.6	TO	9+40.6	RT		0.92				
9+40.6	TO	8+91.1	RT	49.25					
8+91.1	TO	8+68.5	RT				2.35		
8+68.5	TO	8+07.3	RT				12.30		
8+07.3	TO	7+68.5	RT					3.3	1
344+62.5	TO	345+17.5	LT			4.68			
345+17.5	TO	345+49.3	LT				3.19		
345+49.3	TO	348+71	LT	321.5					
348+71	TO	348+83	LT		0.92				
SUBTOTAL =				1627.1	4.60	23.38	38.15	3.3	1
TOTAL =				1627		69.4			1

* SPECIAL INLET TO MEET WITH SIDE ROAD.

TREE REMOVAL (AREA)

LOCATION			LT/RT	TREE REMOVAL (ACRES)
STA.	TO	STA.		
148+73	TO	153+86	LT	0.20
149+50	TO	156+31	RT	0.20
170+04	TO	172+85	LT	0.34
199+30	TO	202+91	LT	0.32
199+01	TO	202+78	RT	0.20
203+30	TO	206+40	LT	0.26
203+25	TO	209+50	RT	0.30
218+45	TO	221+70	LT	0.21
224+70	TO	226+30	LT	0.07
263+60	TO	265+30	LT	0.15
263+00	TO	266+15	RT	0.21
291+64	TO	294+60	LT	0.22
327+80	TO	329+67	RT	0.07
343+90	TO	349+40	LT	0.18
TOTAL				2.93

PLOT DATE = #DATE*
FILE NAME = #FILE*
PLOT SCALE = #SCALE*
REFERENCE = #REF*

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
CONCRETE GUTTER SCHEDULE
TREE REMOVAL SCHEDULE
 FAP ROUTE 809 (IL 158)
 SECTION (133,134)RS-4,135RS-5
 MONROE & ST. CLAIR COUNTIES

SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY _____
 CHECKED BY _____