

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	133,134RS-4,135RS-5	ST. CLAIR, MONROE	252	14
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EARTHWORK SCHEDULE

STA	to	STA	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSED FOR SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
US 158						
141+67.56	to	142+00.00	19.2	14.4	0.0	14.4
142+00.00	to	143+00.00	125.9	94.4	0.0	94.4
143+00.00	to	143+88.52	91.8	68.9	534.4	-465.5
143+88.52	to	144+00.00	7.4	5.6	100.3	-94.7
144+00.00	to	145+00.00	257.4	193.1	270.4	-77.3
145+00.00	to	146+00.00	229.6	172.2	42.6	129.6
146+00.00	to	147+00.00	164.8	123.6	566.7	-443.1
147+00.00	to	147+33.28	149.1	111.8	447.4	-335.6
147+33.28	to	148+00.00	247.1	185.3	869.8	-684.5
148+00.00	to	149+00.00	242.6	182.0	483.3	-301.3
149+00.00	to	150+00.00	413.0	309.8	0.0	309.8
150+00.00	to	151+00.00	375.9	281.9	3.7	278.2
151+00.00	to	152+00.00	303.7	227.8	7.4	220.4
152+00.00	to	153+00.00	475.9	356.9	7.4	349.5
153+00.00	to	154+00.00	457.4	343.1	9.3	333.8
154+00.00	to	155+00.00	318.5	238.9	11.1	227.8
155+00.00	to	156+00.00	175.9	131.9	7.4	124.5
156+00.00	to	157+00.00	137.0	102.8	1.9	100.9
157+00.00	to	157+74.21	236.4	177.3	133.3	44.0
157+74.21	to	158+00.00	67.3	50.5	78.3	-27.8
158+00.00	to	159+00.00	61.1	45.8	124.1	-78.3
159+00.00	to	160+00.00	116.7	87.5	0.0	87.5
160+00.00	to	160+74.42	108.9	81.7	59.3	22.4
160+74.42	to	161+00.00	30.8	23.1	27.0	-3.9
161+00.00	to	162+00.00	131.5	98.6	25.9	72.7
162+00.00	to	163+00.00	270.4	202.8	0.0	202.8
163+00.00	to	164+00.00	388.9	291.7	0.0	291.7
164+00.00	to	165+00.00	374.1	280.6	46.3	234.3
165+00.00	to	166+00.00	183.3	137.5	85.2	52.3
166+00.00	to	167+00.00	42.6	32.0	38.9	-6.9
167+00.00	to	168+00.00	53.7	40.3	0.0	40.3
168+00.00	to	169+00.00	188.9	141.7	0.0	141.7
169+00.00	to	169+55.48	131.5	98.6	0.0	98.6
169+55.48	to	170+00.00	101.4	76.1	0.0	76.1
170+00.00	to	170+50.00	72.2	54.2	5.6	48.6
170+50.00	to	171+00.00	23.1	17.3	123.1	-105.8
171+00.00	to	171+50.00	12.0	9.0	531.5	-522.5
171+50.00	to	172+00.00	12.0	9.0	1465.7	-1456.7
172+00.00	to	172+08.05	1.9	1.4	315.9	-314.5
172+08.05	to	172+50.00	10.1	7.6	1110.9	-1103.3
172+50.00	to	173+00.00	18.5	13.9	485.2	-471.3
173+00.00	to	173+50.00	45.4	34.1	89.8	-55.7
173+50.00	to	174+00.00	66.7	50.0	31.5	18.5
174+00.00	to	175+00.00	103.7	77.8	57.4	20.4
175+00.00	to	175+50.00	32.4	24.3	41.7	-17.4
175+50.00	to	176+00.00	23.1	17.3	92.6	-75.3
176+00.00	to	176+50.00	25.9	19.4	113.9	-94.5
176+50.00	to	177+00.00	19.4	14.6	61.1	-46.5
177+00.00	to	177+50.00	4.6	3.5	41.7	-38.2
177+50.00	to	178+00.00	5.6	4.2	55.6	-51.4
178+00.00	to	178+50.00	6.5	4.9	50.9	-46.0
178+50.00	to	179+00.00	28.7	21.5	51.9	-30.4
179+00.00	to	179+50.00	29.6	22.2	40.7	-18.5
179+50.00	to	180+00.00	63.9	47.9	16.7	31.2
180+00.00	to	180+50.00	226.9	170.2	5.6	164.6
180+50.00	to	181+00.00	313.0	234.8	0.9	233.9
181+00.00	to	181+50.00	223.1	167.3	0.9	166.4
181+50.00	to	182+00.00	163.9	122.9	0.9	122.0
182+00.00	to	182+50.00	205.6	154.2	0.9	153.3
182+50.00	to	183+00.00	201.9	151.4	0.9	150.5
SUB-TOTAL =			7285	5464	8765	-3301

CONTINUED

EARTHWORK SCHEDULE

STA	to	STA	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSED FOR SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
US 158						
183+31.32	to	184+00.00	197.1	147.8	0.0	147.8
184+00.00	to	185+00.00	224.1	168.1	0.0	168.1
185+00.00	to	185+72.15	94.9	71.2	0.0	71.2
185+72.15	to	186+00.00	16.0	12.0	0.0	12.0
186+00.00	to	186+07.93	4.8	3.6	0.0	3.6
186+07.93	to	187+00.00	98.9	74.2	0.0	74.2
187+00.00	to	188+00.00	144.4	108.3	0.0	108.3
188+00.00	to	189+00.00	142.6	107.0	0.0	107.0
189+00.00	to	189+20.74	24.2	18.2	0.0	18.2
189+20.74	to	190+00.00	111.6	83.7	2.9	80.8
190+00.00	to	191+00.00	213.0	159.8	9.3	150.5
191+00.00	to	192+00.00	322.2	241.7	7.4	234.3
192+00.00	to	193+00.00	744.4	558.3	14.8	543.5
193+00.00	to	194+00.00	335.2	251.4	7.4	244.0
194+00.00	to	195+00.00	283.3	212.5	13.0	199.5
195+00.00	to	195+51.00	63.3	47.5	6.6	40.9
195+51.00	to	196+00.00	77.1	57.8	10.0	47.8
196+00.00	to	197+00.00	413.0	309.8	18.5	291.3
197+00.00	to	198+00.00	379.6	284.7	13.0	271.7
198+00.00	to	199+00.00	150.0	112.5	129.6	-17.1
199+00.00	to	199+83.40	151.4	113.6	412.4	-298.8
199+83.40	to	200+00.00	28.9	21.7	135.6	-113.9
201+00.00	to	204+00.00	250.0	187.5	183.3	4.2
204+00.00	to	204+79.00	162.4	121.8	411.1	-289.3
204+79.00	to	205+00.00	61.4	46.1	122.5	-76.4
205+00.00	to	206+00.00	237.0	177.8	94.4	83.4
206+00.00	to	207+00.00	316.7	237.5	20.4	217.1
207+00.00	to	208+00.00	392.6	294.5	14.8	279.7
208+00.00	to	209+00.00	355.6	266.7	16.7	250.0
209+00.00	to	210+00.00	222.2	166.7	283.3	-116.6
210+00.00	to	211+00.00	372.2	279.2	277.8	1.4
211+00.00	to	212+00.00	475.9	356.9	0.0	356.9
212+00.00	to	213+00.00	264.8	198.6	18.5	180.1
213+00.00	to	214+00.00	161.1	120.8	18.5	102.3
214+00.00	to	215+00.00	185.2	138.9	3.7	135.2
215+00.00	to	216+00.00	101.9	76.4	0.0	76.4
216+00.00	to	217+00.00	183.3	137.5	0.0	137.5
217+00.00	to	218+00.00	337.0	252.8	0.0	252.8
218+00.00	to	219+00.00	666.7	500.0	37.0	463.0
219+00.00	to	220+00.00	1025.9	769.4	40.7	728.7
220+00.00	to	221+00.00	1322.2	991.7	5.6	986.1
221+00.00	to	222+00.00	970.4	727.8	14.8	713.0
222+00.00	to	223+00.00	240.7	180.5	18.5	162.0
223+00.00	to	223+37.02	40.4	30.3	7.5	22.8
223+37.02	to	224+00.00	172.6	129.5	38.5	91.0
224+00.00	to	225+00.00	257.4	193.1	77.8	115.3
225+00.00	to	225+76.92	314.8	236.1	131.0	105.1
225+76.92	to	226+00.00	82.5	61.9	83.3	-21.4
226+00.00	to	227+00.00	48.1	36.1	350.0	-313.9
227+00.00	to	228+00.00	153.7	115.3	181.5	-66.2
228+00.00	to	229+00.00	768.5	576.4	63.0	513.4
229+00.00	to	230+00.00	1227.8	920.9	14.8	906.1
230+00.00	to	231+00.00	968.5	726.4	5.6	720.8
231+00.00	to	232+00.00	614.8	461.1	3.7	457.4
232+00.00	to	233+00.00	424.1	318.1	3.7	314.4
233+00.00	to	234+00.00	301.9	226.4	11.1	215.3
234+00.00	to	235+00.00	213.0	159.8	18.5	141.3
235+00.00	to	236+00.00	146.3	109.7	20.4	89.3
236+00.00	to	237+00.00	140.7	105.5	16.7	88.8
237+00.00	to	238+00.00	135.2	101.4	22.2	79.2
238+00.00	to	239+00.00	63.0	47.3	24.1	23.2
239+00.00	to	239+86.87	41.8	31.4	14.5	16.9
239+86.87	to	240+00.00	9.2	6.9	2.2	4.7
SUB-TOTAL =			18650	13988	3453	10536

CONTINUED

PLOT DATE = #DATE#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 REFERENCE = #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
EARTHWORK SCHEDULE SHEET #1
 FAP ROUTE 809 (IL RTE. 158)
 SECTION (133, 134)RS-4, 135RS-5
 ST. CLAIR AND MONROE COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____