

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	133,134RS-4,135RS-5	ST. CLAIR, MONROE	252	15
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

EARTHWORK SCHEDULE

STA	to	STA	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
US 158						
240+84.99	to	241+00.00	11.7	8.8	16.7	-7.9
241+00.00	to	241+50.00	65.7	49.3	65.7	-16.4
241+50.00	to	242+00.00	82.4	61.8	25.0	36.8
242+00.00	to	242+50.00	100.9	75.7	0.9	74.8
242+50.00	to	242+98.67	119.9	89.9	18.9	71.0
242+98.67	to	243+50.00	99.8	74.9	39.0	35.9
243+50.00	to	244+50.00	90.7	68.0	51.9	16.1
244+50.00	to	245+00.00	39.8	29.9	13.0	16.9
245+00.00	to	245+50.00	48.1	36.1	16.7	19.4
245+50.00	to	246+00.00	51.9	38.9	17.6	21.3
246+00.00	to	246+50.00	46.3	34.7	15.7	19.0
246+50.00	to	247+00.00	47.2	35.4	9.3	26.1
247+00.00	to	247+50.00	157.4	118.1	22.2	95.9
247+50.00	to	248+00.00	114.8	86.1	6.5	79.6
248+00.00	to	248+50.00	147.2	110.4	38.0	72.4
248+50.00	to	249+00.00	97.2	72.9	32.4	40.5
249+00.00	to	250+00.00	163.0	122.3	0.0	122.3
250+00.00	to	250+50.00	133.3	100.0	0.0	100.0
250+50.00	to	251+00.00	135.2	101.4	0.0	101.4
251+00.00	to	252+00.00	266.7	200.0	0.0	200.0
252+00.00	to	252+50.00	148.1	111.1	0.0	111.1
252+50.00	to	253+00.00	180.6	135.5	0.0	135.5
253+00.00	to	253+50.00	167.6	125.7	0.9	124.8
253+50.00	to	254+00.00	152.8	114.6	0.9	113.7
254+00.00	to	255+00.00	311.1	233.3	0.0	233.3
255+00.00	to	255+50.00	141.7	106.3	2.8	103.5
255+50.00	to	256+00.00	124.1	93.1	5.6	87.5
256+00.00	to	256+50.00	111.1	83.3	6.5	76.8
256+50.00	to	257+00.00	104.6	78.5	7.4	71.1
257+00.00	to	257+46.28	99.4	74.6	6.0	68.6
257+46.28	to	258+00.00	125.3	94.0	4.0	90.0
258+00.00	to	259+00.00	259.3	194.5	1.9	192.6
259+00.00	to	260+00.00	246.3	184.7	9.3	175.4
260+00.00	to	261+00.00	216.7	162.5	18.5	144.0
261+00.00	to	262+00.00	205.6	154.2	13.0	141.2
262+00.00	to	263+00.00	283.3	212.5	20.4	192.1
263+00.00	to	264+00.00	381.5	286.1	48.1	238.0
264+00.00	to	264+59.24	181.0	135.8	70.2	65.6
264+59.24	to	265+00.00	122.3	91.7	67.2	24.5
265+00.00	to	266+00.00	413.0	309.8	129.6	180.2
266+00.00	to	267+00.00	255.6	191.7	188.9	2.8
267+00.00	to	268+00.00	172.2	129.2	144.4	-15.2
268+00.00	to	269+00.00	244.4	183.3	16.7	166.6
269+00.00	to	270+00.00	163.0	122.3	7.4	114.9
270+00.00	to	271+00.00	133.3	100.0	0.0	100.0
271+00.00	to	271+50.00	72.2	54.2	1.9	52.3
271+50.00	to	272+00.00	90.7	68.0	6.5	61.5
272+00.00	to	272+50.00	116.7	87.5	14.8	72.7
272+50.00	to	273+00.00	71.3	53.5	26.9	26.6
273+00.00	to	273+50.00	67.6	50.7	42.6	8.1
273+50.00	to	274+00.00	106.5	79.9	56.5	23.4
274+00.00	to	274+50.00	107.4	80.6	63.9	16.7
274+50.00	to	275+00.00	101.9	76.4	75.9	0.5
275+00.00	to	275+50.00	99.1	74.3	88.9	-14.6
275+50.00	to	276+00.00	97.2	72.9	79.6	-6.7
276+00.00	to	276+50.00	81.5	61.1	69.4	-8.3
276+50.00	to	277+00.00	85.2	63.9	59.3	4.6
277+00.00	to	278+00.00	259.3	194.5	72.2	122.3

STA	to	STA	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
278+00.00	to	278+50.00	149.1	111.8	49.1	62.7
278+50.00	to	279+00.00	92.6	69.5	38.0	31.5
279+00.00	to	279+50.00	40.7	30.5	5.6	24.9
279+50.00	to	280+00.00	36.1	27.1	76.9	-49.8
280+00.00	to	280+50.00	31.5	23.6	100.9	-77.3
280+50.00	to	281+00.00	36.1	27.1	50.0	-22.9
281+00.00	to	281+50.00	48.1	36.1	42.6	-6.5
281+50.00	to	282+00.00	48.1	36.1	39.8	-3.7
282+00.00	to	282+50.00	51.9	38.9	35.2	3.7
282+50.00	to	283+00.00	59.3	44.5	28.7	15.8
283+00.00	to	283+50.00	81.5	61.1	23.1	38.0
283+50.00	to	284+00.00	103.7	77.8	17.6	60.2
284+00.00	to	284+50.00	110.2	82.7	13.0	69.7
284+50.00	to	285+00.00	115.7	86.8	7.4	79.4
285+00.00	to	285+50.00	87.0	65.3	1.9	63.4
SUB-TOTAL =			8561	6422	1905	4517

CONTINUED

CONTINUED

PLOT DATE = #DATE#  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 REFERENCE = #REF#

REVISIONS		DATE
NAME		

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**EARTHWORK SCHEDULE**  
**SHEET #2**  
 FAP ROUTE 809 (IL RTE. 158)  
 SECTION (133, 134)RS-4, 135RS-5  
 ST. CLAIR AND MONROE COUNTY

SCALE: VERT. _____	DRAWN BY _____
DATE _____	CHECKED BY _____