CONTRACT NO. 76408

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-4,135RS-5	ST. CLAIR, MONROE	252	20
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

CROSS ROAD CULVERT SCHEDULE

		CULV. NO.**	CON-CRETE COLLAR	PR CONCRETE END SECTIONS	PR CONCRETE END SECTIONS	PR CONCRETE END SECTIONS	BOX CULVERT END SECTION, CULVERTS #2,3,4,8,10	BOX CULVERT END SECTION, CULVERT #1	BOX CULVERT END SECTION, CULVERT #5	BOX CULVERT END SECTION, CULVERT #6	BOX CULVERT END SECTION, CULVERT #7	BOX CULVERT END SECTION, CULVERT #9	PC CONCRETE BOX CULVERT	PC CONCRETE BOX CULVERT	PC CONCRETE BOX CULVERT	PC CONCRETE BOX CULVERT	PC CONCRETE BOX CULVERT	PC CONCRETE BOX CULVERT	PIPE CULVERTS, CLASS A TYPE 2				MANHOLES, TYPE A, TYPE 1 FRAME, CLOSED LID		OUTLET TYPE 1 FOR TYPE A GUTTER	GRATE, TYPE A	STORM SEWERS, CLASS A, TYPE 1	COMMENTS
LOCATION	LT/RT			15"	18"	36"	2'X1.5'	2'X2'	5'X7'	7'X2'	4'X2'	5'X4'	2'X1.5'	2'X2'	5'X7'	7'X2'	4'X2'	5'X4'	12"	15"	18"	36"	5' DIA	6' DIA.			12"	
(STA)			(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(FOOT)	
143+90	LT		1		1																42.9							
143+90	RT		1		1																8							
147+23	LT	1	1					1						38														
147+23	RT		1					1						18.8														
157+74	LT		1		1																18.5							
157+74	RT		1		1																10							
160+74	LT		1		1																11							
160+74	RT		1		1																6.5							
172+00	LT	2	1				1						44															
172+00	RT		1				1						22															
177+50	LT																			160								COLUMBIA QUARRY RD.
199+83	LT	3	1				1						19															
199+83	RT		1				1						10															
204+80	LT	4	1				1						19.3															
204+80	RT		1				1						9															
223+37	RT	10	1				1						5															
225+77*	LT/RT																											
242+99	LT		1	1																4								
242+99	RT		1	1																10								
248+00	LT/RT				2																72							
249+00	LT																								1	1	64	TRIPLE LAKES RD.
249+00	RT																			115								BOHLEYSVILLE RD.
264+59	LT	5	1						1						8													
264+59	RT		1						1						8													
293+60	LT	6	1							1						8.3												
293+60	RT		1							1						16.2												
304+13	LT	7	1								1						7											
304+13	RT		1								1						15											
325+45**	LT	8	1				1						5															
325+45**	RT		1			1							5						45			9		1				
335+05**	LT		1																	68	3		1					
335+05**	RT		1		1																12.6							
365+47	LT	9	1									1						10										
365+47	RT		1									1						8										
TOTAL =			29	2	9	1	8	2	2	2	2	2	133.3	56.8	16	24.5	22	18	45	357	184.5	9	1	1	1	1	64	

*CAST-IN-PLACE BOX CULVERT EXTENSIONS-SEE DETAIL SHEETS FOR SCHEDULE OF QUANTITIES

** SEE DETAIL SHEETS

*** SEE BOX CULVERT END SECTIONS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

CROSS ROAD CULVERT SCHEDULE

FAP ROUTE 809 (IL 158)
SECTION (133,134)RS-4,135RS-5
MONROE & ST. CLAIR COUNTIES

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 1/7/2009
FILE NAME = c:\pw_work\PWIDOT\KARLASAL\dms51225\sch01902.dgn
PLOT SCALE = 50.0000 ' / IN.
REFERENCE = REF