CONTRACT NO. 76408

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-4,135RS-5	ST. CLAIR, MONROE	252	21A
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

CONTINUED FROM PREVIOUS SHEET

SIGN SCHEDULE

LOCATION STATION	LOCATION OFFSET		MESSAGE	SIGN NUMBER	SIZE	POST TYPE	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY (POUND)	REINFORCEMENT BARS (POUND)	CONCRETE STRUCTURES (CU YD)	WOOD POST (FT)	METAL POST - TYPE A (FT)	SIGN PANEL TYPE I (SQ FT)	SIGN PANEL TYPE II (SQ FT)	SIGN PANEL TYPE III (SQ FT)	RELOCATE SIGN PANEL TYPE I (SQ FT)	RELOCATE SIGN PANEL ASSEMBLY TYPE A (SQ FT)	RELOCATE SIGN PANEL ASSEMBLY TYPE B (SQ FT)
IL 158																	
248+77	42.4	LT	STOP	R1-1	3' X 3'	WOOD POST				16.5		12.75					
			CROSS TRAFFIC DOES NOT STOP	R1-I100	2.5' X 1.5'												
248+86	170.9	RT	ST CLAIR COUNTY ROAD SIGN	M1-60	2' X 2'	METAL POST					12.5				4		
249+41	54.7	RT	STOP	R1-1	3' X 3'	WOOD POST				16.5		12.75					
			CROSS TRAFFIC DOES NOT STOP	R1-I100	2.5' X 1.5'												
249+61	162.8	LT	VAR SIGNS	VAR	-	METAL POST				16.5						9	
249+65	30.0	LT	IL 158 (2)	UNIQUE	2' X 0.75'	METAL POST					12					6	
			TRIPLE LAKES RD (2)	UNIQUE	2' X 0.75'												
251+00	42.0	RT	SPEED LIMIT 55	R2-1	2.5' X 3'	WOOD POST				15		7.5					
252+25	30.0	LT	CROSS ROADS	W2-1	3' X 3'	WOOD POST				16.5		15.75					
			TRIPLE LAKES RD, BOHLEYSVILLE RD	UNIQUE	4.5' X 1.5'												
252+25	42.0	RT	IL 158	M1-I100	2.5' X 2'	WOOD POST				14		5					
266+15	30.0	LT	STOP	R1-1	3' X 3'	WOOD POST				15		9					
266+60	30.0	LT	PRAIRIE DR	UNIQUE	2' X 0.5'	METAL POST					11				2		
271+22	30.0	RT	LEFT CURVE, SIDE ROAD	W1-10L	3' X 3'	WOOD POST				17		12.5					
			DOUGLAS ROAD	UNIQUE	3.5' X 1'												
275+00	30.0	LT	SPEED LIMIT 55	R2-1	2.5' X 3'	WOOD POST				15		7.5					
275+56	46.0	RT	FREEBURG - ARROW - 13	D2-1	6.5' X 1.5'	WOOD POST				27			9.75				
277+25	38.5	LT	IL 158	M1-I100	2.5' X 2'	WOOD POST				14		5					
279+25	36.0	LT	DOUBLE ARROW	W1-7	4' X 2'	WOOD POST				14		8					
279+47	30.4	RT	STOP	R1-1	3' X 3'	WOOD POST				16.5		12.75					
			CROSS TRAFFIC DOES NOT STOP	R1-I100	2.5' X 1.5'												
279+89	47.0	RT	STOP	R1-1	3' X 3'	WOOD POST				16.5		12.75					
			CROSS TRAFFIC DOES NOT STOP	R1-I100	2.5' X 1.5'												
280+37	77.6	RT	JB BRIDGE, COLUMBIA, MILLSTADT	UNIQUE	4.5' x 2.5'	WOOD POST				14.5			11.25				
281+25	36.0	LT	IL 158	M1-I100	2.5' X 2'	WOOD POST				16.5		12.75					
			ST CLAIIR, IL 158, MM 2	XM-1	1.5' X 1.5'												
282+95	36.0	LT	FREEBURG - ARROW - 13	D2-1	6.5' X 1.5'	WOOD POST				27			9.75				
283+50	30.0	RT	SPEED LIMIT 55	R2-1	2.5' X 3'	WOOD POST				15		7.5					
285+95	30.0	LT	LEFT CURVE, SIDE ROAD	W1-10L	3' X 3'	WOOD POST				17		12.5					
			DOUGLAS ROAD	UNIQUE	3.5' X 1'												
290+58	30.0	RT	SIGNS FROM STA 291+04	UNIQUE	2.5' X 0.5'	METAL POST					11	2.5					
291+13	30.0	RT	STOP	R1-1	3' X 3'	WOOD POST				15		9					
292+75	30.0	RT	SIGNS FROM STA 292+72	UNIQUE	VAR	WOOD POST				20.5							20.25
309+20	30.0	LT	STOP	R1-1	3' X 3'	WOOD POST				15		9					
324+30	30.0	RT	SIGNS FROM STA 324+29	10985, 10986	2.5' X 3.25'	WOOD POST				15.25		8.125					
324+30	30.0	LT	SIGNS FROM STA 324+30	10985, 10987	2.5' X 3.25'	WOOD POST				15.25		8.125					
329+00	30.0	LT	NO PASSING ZONE	W14-3	4' X 3'	WOOD POST				16		6					
336+70	30.0	RT	ST CLAIR COUNTY, IL 158, MM3	XM-1	1.5' X 1.5'	WOOD POST				13.5		4.5					
356+00	30.0	RT	SPEED SONE AHEAD	R2-5C	2' X 2.5'	WOOD POST				16		7.25					
			35 MPH	W13-1	1.5' X 1.5'												
361+00	30.0	RT	SPEED LIMIT 35	R2-1	2.5' X 3'	WOOD POST				15		7.5					
361+00	30.0	LT	SPEED LIMIT 55	R2-2	2.5' X 3'	WOOD POST				15		7.5					
363+00	30.0	LT	SIGNS FROM STA 363+03	UNIQUE	VAR	WOOD POST				20.5							20.25
366+60	30.0	RT	SIGNS FROM STA 366+65	UNIQUE	2' X 0.5'	METAL POST					11						
367+00	30.0	LT	COLUMBIA, JB BRIDGE	UNIQUE	5' X 2.5'	WOOD POST				14.5			12.5				
367+12	30.0	RT	STOP	R1-1	3' X 3'	WOOD POST				15		9					
DOUGLAS RD																	
11+00	30.0	RT	SPEED LIMIT - 55 MPH	R2-1	2.5' X 3'	WOOD POST				15		7.5					
TOTALS							1733.6	368	4.72	994.8	94	483	58.25	323.75	18.5	30	40.5

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 809 (IL 158)
SECTION (133,134)RS-4,135RS-5
MONROE & ST. CLAIR COUNTIES

SCALE: VERT. HORIZ. DRAWN BY
DATE CHECKED BY

PLOT DATE = $DATE$
FILE NAME = $$FILEL$
PLOT SCALE = $$SCALE$
REFERENCE = REF