CONTINUED FROM PREVIOUS SHEET

SIGN REMOVAL SCHEDULE

LOCATION STATION	LOCATION OFFSET	MESSAGE	SIGN NUMBER	SIZE	POST TYPE	REMOVE GROUND MOUNTED SIGN SUPPORT EACH	REMOVE CONCRETE FOUNDATION - GROUND MOUNT EACH	REMOVE SIGN PANEL TYPE I SQ FT	REMOVE SIGN PANEL TYPE II SQ FT	REMOVE SIGN PANEL TYPE III SQ FT	REMOVE SIGN PANEL ASSEMBLY TYPE A SQ FT	REMOVE SIGN PANEL ASSEMBLY TYPE B SQ FT
IL 158												
249+65	36.7 RT	STOP	R1-1	2.5' X 2.5'	METAL	1		6.25				
250+00	24.0 LT	NO PARKING	R8-3	1' X 1.5'	METAL	1		1.5				
250+85	31.4 LT	UNIQUE	UNIQUE	4' X 4'	WOOD	1			16			
251+67	31.8 LT	UNIQUE	UNIQUE	4' X 4'	WOOD	1			16			
252+44	30.1 RT	IL 158	M1-I100	2.5' X 2'	METAL	1		5				
255+53	34.1 LT	UNIQUE	UNIQUE	4' X 4'	WOOD	1			16			
256+95	27.7 LT	CROSS ROAD	W2-1	2.5' X 2.5'	WOOD	1						1
		TRIPLE LAKES ROAD, BELLEVILLE ROAD	UNIQUE	3' X 1'								
258+64	29.5 RT	NO PASSING ZONE	W14-13	4' X 3'	METAL	2		6				
265+66	30.0 RT	CURVE, LEFT	W1-2L	3' X 3'	METAL	1		9				
266+21	36.1 LT	STOP	R1-1	2.5' X 2.5'	METAL	1		6.25				
266+68	30.1 LT	2 - PRARIE DRIVE	UNIQUE	2' X 0.5	METAL	1		2				
271+74	29.3 RT	SIDE ROAD - PERPENDICULAR	W2-2	3' X 3'	WOOD	1						1
		DOUGLAS ROAD	UNIQUE	3' X 1.25'								
276+96	21.5 LT	IL 158	M1-I100	2.5' X 2'	WOOD	1		5				
277+48	28.9 RT	FREEBURG 13	UNIQUE	4' X 1'	METAL	1		4				
278+85	30.2 LT	LARGE ARROW - TWO DIRECTIONS	W1-7	5' x 2.5'	WOOD	2			10			
281+23	22.6 RT	IL 158	M1-I100	2.5' X 2'	METAL	1		5				
281+99	29.2 LT	FREEBURG 13	UNIQUE	6 X 1.5'	WOOD	1		9				
283+53	23.3 RT	2 - IL 158 ST. CLAIR COUNTY	XM-1	1.5' X 1.5'	METAL	1					1	
284+16	31.7 LT	CURVE, RIGHT	W1-2R	2.5' X 2.5'	WOOD	1		6.25				
286+44	28.3 LT	SIDE ROAD - PERPENDICULAR	W2-2	3' X 3'	WOOD	1						1
		DOUGLAS ROAD	UNIQUE	3' X 1.25'								
291+04	39.8 RT	ROENKKE ROAD	UNIQUE	2.5' X 0.5'	WOOD						1	
		STOP	R1-1	2.5' X 2.5'								
292+72	27.8 RT	LOVE THE LAND OF LINCOLN	UNIQUE	2.5' X 3'	METAL	1						1
		ADOPT A HIGHWAY, CIVIC CLUB	UNIQUE	2.5' X 1.5'								
		KEEP ILLINOIS CLEAN	UNIQUE	3' X 3'								
309+28	33.8 LT	ALBERT LN	UNIQUE	2' X 0.5'	WOOD	1					1	
		STOP	R1-1	2.5' X 2.5'								
322+51	26.4 RT	TRUCK	W11-10	2.5' X 2.5'	METAL	1		6.25				
324+29	25.6 LT	WATER SUPPLY PROTECTION AREA		2.5' X 2.5'	METAL	1					1	
		REPORT SPILLS		2.5' X 0.75'								
324+29	26.6 RT	WATER SUPPLY PROTECTION AREA		2.5' X 2.5'	METAL	1					1	
		REPORT SPILLS		2.5' X 0.75'								
325+46	23.5 RT	BESSE LANE	UNIQUE	2.0' X 0.5'	METAL	1		1				
329+02	30.2 LT	NO PASSING ZONE	W14-13	4' X 3'	WOOD	1		6				
336+66	21.5 RT	2 - IL 158 ST. CLAIR COUNTY	XM-1	1.5' X 1.5'	METAL	1					1	
346+83	25.1 LT	TRUCK	W11-10	2.5' X 2.5'	METAL	1		6.25				
351+17	32.3 RT	NO PASSING ZONE	W14-13	4' X 3'	METAL	1		6				
355+91	31.8 RT	SPEED ZONE AHEAD	R2-5C	2' X 2.5'	WOOD	1					1	
		ADVISORY SPEED PLATE, 35 MPH	W13-1	1.5' X 1.5'								
359+47	27.0 RT	SIDE ROAD - PERPENDICULAR	W2-2	2.5' X 2.5'	METAL	1		6.25				
360+93	31.5 LT	SPEED LIMIT - 55 MPH	R2-1	2.5' X 3'	METAL	1		7.5				
363+03	27.0 LT	LOVE THE LAND OF LINCOLN	UNIQUE	2.5' X 3'	METAL	1						1
		ADOPT A HIGHWAY, CIVIC CLUB	UNIQUE	2.5' X 1.5'								
		KEEP ILLINOIS CLEAN	UNIQUE	3' X 3'								
365+64	26.9 RT	SPEED LIMIT - 35 MPH	R2-1	2' X 2.5'	WOOD	1		5				
366+89	29.0 LT	COLUMBIA, JB BRIDGE	UNIQUE	5' x 2.5'	WOOD	2			12.5			
367+12	30.0 RT	STOP	R1-1	3' X 3'	WOOD	1		9			1	
DOUGLAS RD												
5+18	3.2 RT	STOP	R1-1	3' X 3'	WOOD	1						1
		CROSS TRAFFIC DOES NOT STOP	R1-I100	3' X 1.5'								
		DOUGLAS ROAD	⚠	⚠								
5+38	27.4 LT	STOP	R1-1	2.5' X 2.5'	WOOD	1		6.25				
6+28	16.7 LT	JB BRIDGE, MILLSTADT	UNIQUE	4' X 2.5'	WOOD	1			10			
11+07	23.3 RT	SPEED LIMIT - 55 MPH	R2-1	2.5' X 3'	WOOD	1		7.5				
TOTAL						91	2	258.25	95.5	150	16	17

SOME SIGNS THAT ARE REMOVED MAY BE RE-ERECTED IN NEW LOCATION, SEE SIGN SCHEDULE
ANY SIGNS THAT ARE NOT REUSED SHALL BE DELIVERED TO THE SIGN SHOP

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 809 (IL 158)
SECTION (133,134)RS-4,135RS-5
MONROE & ST. CLAIR COUNTIES

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = $DATE$
FILE NAME = $FILE$
PLOT SCALE = $SCALE$
REFERENCE = REF