

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		ROADWAY I000-2A	STRUCTURE X071-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	40	40	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	122	122	
20200100	EARTH EXCAVATION	CU YD	225	225	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	80	80	
20300100	CHANNEL EXCAVATION	CU YD	3440	3440	
20400800	FURNISHED EXCAVATION	CU YD	625	625	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	127		127
25000200	SEEDING, CLASS 2	ACRE	1.75	1.75	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	136	136	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	136	136	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	136	136	
25100105	MULCH, METHOD 1	ACRE	4.75	4.75	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	275	275	
28000300	TEMPORARY DITCH CHECKS	EACH	5	5	
28000400	PERIMETER EROSION BARRIER	FOOT	1082	1082	
28000500	INLET AND PIPE PROTECTION	EACH	4	4	
28100109	STONE RIPRAP, CLASS A5	SQ YD	2821		2821
28200200	FILTER FABRIC	SQ YD	2821		2821
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	43	43	
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	268	268	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.7	0.7	
40600300	AGGREGATE (PRIME COAT)	TON	4	4	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	97	97	
40600990	TEMPORARY RAMP	SQ YD	27	27	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	255	255	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	174	174	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	17	17	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	25	25	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	31	31	
44000100	PAVEMENT REMOVAL	SQ YD	519	519	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	945	945	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	31	31	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	468	468	
48203005	HOT-MIX ASPHALT SHOULDERS, 2"	SQ YD	184	184	
48203033	HOT-MIX ASPHALT SHOULDERS, 9"	SQ YD	359	359	

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		ROADWAY I000-2A	STRUCTURE X071-2A
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	185	185	
50200100	STRUCTURE EXCAVATION	CU YD	471		471
50300100	FLOOR DRAINS	EACH	26		26
50300225	CONCRETE STRUCTURES	CU YD	296.9		296.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	473.1		473.1
50300260	BRIDGE DECK GROOVING	SQ YD	1561		1561
50300280	CONCRETE ENCASEMENT	CU YD	21.8		21.8
50300300	PROTECTIVE COAT	SQ YD	1981		1981
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	2270		2270
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	12010		12010
50500505	STUD SHEAR CONNECTORS	EACH	6552		6552
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	154940		154940
50800515	BAR SPLICERS	EACH	1406		1406
51201610	FURNISHING STEEL PILES HP12X63	FOOT	775		775
51201900	FURNISHING STEEL PILES HP14X89	FOOT	2268		2268
51202305	DRIVING PILES	FOOT	3043		3043
51203610	TEST PILE STEEL HP12X63	EACH	2		2
51203900	TEST PILE STEEL HP14X89	EACH	4		4
51205200	TEMPORARY SHEET PILING	SQ FT	3403		3403
51500100	NAME PLATES	EACH	1		1
52100520	ANCHOR BOLTS, 1"	EACH	72		72
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1	1	
54213450	END SECTIONS 15"	EACH	7	7	
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	190	190	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	68		68
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	152		152
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	225	225	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	650	650	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	22	22	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9	

*SPECIALTY ITEMS

FILE NAME =	USER NAME = gelinh	DESIGNED - HG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pw_work\pwwd\gelinh\dms51845\p1n00326a.dgn		DRAWN - HG	REVISED -			805	126-BR-1	CLINTON	85	3	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 76976					
PLOT DATE = 12/9/2008		DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

Rev.