

SHOULDER & PAVEMENT SCHEDULE

LOCATION	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	GUTTER REMOVAL	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE	HOT-MIX ASPHALT SURFACE COURSE	HOT-MIX ASPHALT SHOULDERS, 9"	CLASS SI CONCRETE (OUTLET)
STATION TO STATION	SQ YD	SQ YD	FOOT	SQ YD	TON	TON	TON	TON	SQ YD	CU YD
SN 031-2012										
STA 1065+00 TO STA 1066+00				61.6						
STA 1066+00 TO STA 1067+00				66.7						
STA 1067+00 TO STA 1068+00	37.6			60.7	0.02	0.08	27.3	3.2		
STA 1068+00 TO STA 1069+00	92.4			13.9	0.08	0.42	174.7	20.1		
STA 1069+00 TO STA 1070+00				66.7						
STA 1070+00 TO STA 1071+00				66.7						
STA 1071+00 TO STA 1072+00				26.7						
SN 031-0042										
STA 1120+00 TO STA 1121+00		288.8		66.8	0.08	0.43		24.3	66.7	
STA 1121+00 TO STA 1122+00		114.1		66.8	0.09	0.43	73.5	24.3	66.7	
STA 1122+00 TO STA 1123+00				81.2	0.07	0.35	96.7	19.1	52.6	
STA 1123+00 TO STA 1124+00	127.2			19.5						
STA 1124+00 TO STA 1125+00	5.8			71.3	0.06	0.28	120.2	14.9	41.3	
STA 1125+00 TO STA 1126+00				74.1	0.09	0.43	193.8	24.3	66.7	
STA 1126+00 TO STA 1127+00		77.0	175	33.3	0.08	0.43	148.8	24.3	66.7	8.2
STA 1127+00 TO STA 1128+00		101.1	70		0.03	0.15		8.5	23.3	2.8
TOTAL	263	581	245	776	0.6	3	835	163	384	11

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR 25% SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
CU YD	CU YD	CU YD	CU YD	CU YD
SN 031-2012				
STA 1064+00 TO STA 1065+00	0.3	0.2	5.1	-4.9
STA 1065+00 TO STA 1066+00	6.5	4.9	224.4	-219.5
STA 1066+00 TO STA 1067+00	7.4	5.6	387.3	-381.7
STA 1067+00 TO STA 1068+00	3.4	2.7	358.2	-355.5
STA 1068+00 TO STA 1069+00	1.1	0.9	117.3	-116.4
STA 1069+00 TO STA 1070+00	5.4	4.0	248.3	-244.3
STA 1070+00 TO STA 1071+00	6.1	4.6	185.8	-181.2
STA 1071+00 TO STA 1072+00	18.7	14.1	12.7	+1.4
STA 1072+00 TO STA 1073+00	9.8	7.4	0.3	+7.1
SN 031-0042				
STA 1119+00 TO STA 1120+00	2.2	1.7	3.1	-1.4
STA 1120+00 TO STA 1121+00	8.1	6.1	81.9	-75.8
STA 1121+00 TO STA 1122+00	3.3	2.5	222.1	-219.6
STA 1122+00 TO STA 1123+00	0.1	0.1	426.7	-426.6
STA 1123+00 TO STA 1124+00	0.0	0.0	96.9	-96.9
STA 1124+00 TO STA 1125+00	0.0	0.0	757.2	-757.2
STA 1125+00 TO STA 1126+00	0.2	0.2	355.2	-355.0
STA 1126+00 TO STA 1127+00	17.4	13.1	15.6	-2.5
TOTAL	90	68.1	3498.1	-3430.0

PAVEMENT MARKING SCHEDULE

LOCATION	PAVEMENT MARKING REMOVAL			SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING	THERMOPLASTIC PAVEMENT MARKING -4"			POLYUREA PAVEMENT MARKING TYPE I-LINE 4"			RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	REPLACEMENT REFLECTOR	
	YELLOW		WHITE			YELLOW		WHITE		PAVEMENT MARKER REMOVAL	PAVEMENT MARKER					PAVEMENT MARKER (BRIDGE)
	SKIP-DASH	SOLID	SOLID			SKIP-DASH	SOLID	SOLID								
STATION TO STATION	SQ FT	SQ FT	SQ FT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	
SN 031-2012																
STA 1064+00 TO STA 1065+00	1.9		15.3	12	4.0	5.8		46				1			1	
STA 1065+00 TO STA 1066+00	8.3		66.7	16	5.3	25		200				1			1	
STA 1066+00 TO STA 1067+00	8.3		66.7	16	5.3	25		200				1			1	
STA 1067+00 TO STA 1068+00	8.3		66.7	20	6.7	25		200					1			
STA 1068+00 TO STA 1069+00	8.3		66.7	16	5.3	25		200								
STA 1069+00 TO STA 1070+00	8.3		66.7	16	5.3	25		200				1			1	
STA 1070+00 TO STA 1071+00	8.3		66.7	16	5.3	25		200				1			1	
STA 1071+00 TO STA 1072+00	7.3		58.1	16	5.3	21.7		174				1			1	
SN 031-0042																
STA 1119+00 TO STA 1120+00	5.2	20.8	41.7	12	4.0	15.6	62.5	125				1	1			
STA 1120+00 TO STA 1121+00	8.3	33.3	66.7	16	5.3	25	100	200				1	1			
STA 1121+00 TO STA 1122+00	8.3	33.3	66.7	16	5.3	25	100	200				1	1			
STA 1122+00 TO STA 1123+00	5.7	34.1	56.7	20	6.7	16.9	102	170		30.0	30.0			1		
STA 1123+00 TO STA 1124+00				16	5.3				24.5	102.5	200.0			1		
STA 1124+00 TO STA 1125+00	5.8	22.7	45.3	16	5.3	17	68	136	8.0	32.0	64.0		1			
STA 1125+00 TO STA 1126+00	8.3	33.3	66.7	20	6.7	25	100	200					1			
STA 1126+00 TO STA 1127+00	8.3	33.3	66.7	16	5.3	25	100	200				2	2			
STA 1127+00 TO STA 1128+00	8.2	32.7	65.3	16	5.3	24.5	98	196				1	1			
SUBTOTAL	117.1	243.5	949.4			351.5	730.5	2847	32.5	164.5	294.0					
TOTAL		1310		276	92	3929			491			12	10	2	6	

REPLACEMENT REFLECTORS (REMOVED DURING STAGE CONSTRUCTION) ARE FROM STOP BAR TO STOP BAR.
 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL REQUIRES ONLY THE REFLECTORS TO BE REMOVED.

Rev. 2-18-09