

EROSION CONTROL SCHEDULE

LOCATION	PERIMETER EROSION BARRIER	TEMPORARY EROSION CONTROL SEEDING
QUADRANT	FOOT	POUND
SN 031-2012		
NORTHWEST	331	40.3
NORTHEAST	429	34.4
SOUTHWEST	434	36.1
SOUTHEAST	379	29.2
SN 031-0042		
NORTHWEST	379	28.8
NORTHEAST	415	25.8
SOUTHWEST	403	26.8
SOUTHEAST	408	28.6
TOTAL	3178	250

TREE REMOVAL SCHEDULE

LOCATION	TREE REMOVAL
QUADRANT	ACRE
SN 031-2012	
NORTHWEST	0.03
NORTHEAST	0.05
SOUTHWEST	0.06
SOUTHEAST	0.05
SN 031-0042	
NORTHWEST	0.01
NORTHEAST	0.02
SOUTHWEST	0.01
SOUTHEAST	0.02
TOTAL	0.25

STAGING SCHEDULE

LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	TEMPORARY PAVEMENT MARKING - LINE 6"	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE)	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE)	TEMPORARY BRIDGE TRAFFIC SIGNALS	TEMPORARY RUMBLE STRIP
	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH
SN 031-2012			375			1	6
STAGE I		350		2			
STAGE II	375				2		
SN 031-0042			537.5			1	6
STAGE I	537.5			2			
STAGE II		512.5			2		
TOTAL	912.5	862.5	912.5	4	4	2	12

GUARDRAIL SCHEDULE

LOCATION	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURE	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	TRAFFIC BARRIER TERMINAL, TYPE 6	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKERS - DIRECT APPLIED
	FOOT	FOOT		EACH	EACH	EACH	EACH	EACH	EACH	EACH
SN 031-2012										
NW QUADRANT	57.9	112.5			1					
NE QUADRANT	57.4	200			1					
SW QUADRANT	57.7	200			1					
SE QUADRANT	57.0	112.5			1					
EASTBOUND			42				5			
WESTBOUND			42				5			
SN 031-0042										
NW QUADRANT	65.7	75			1	1				
NE QUADRANT	60.5	125		1		1				1
SW QUADRANT	59.7	175			1	1				
SE QUADRANT	66.1	75			1	1				
EASTBOUND							6	1	1	
WESTBOUND							5	1	1	
TOTAL	482	1075	84	1	7	4	21	2	2	1

RIGHT-OF-WAY MARKERS SCHEDULE

LOCATION	LT OR RT	OFFSET DISTANCE	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	DRAINAGE MARKERS	PERMANENT SURVEY MARKERS
STATION		FOOT	EACH	EACH	EACH
STA. 1059+07.88					1
STA. 1063+91.34	LT	39.63	1		
STA. 1063+92.84	RT	40.37	1		
STA. 1065+50.00	LT	54.67	1		
STA. 1065+50.00	RT	55.33	1		
STA. 1068+15.00	RT	55.25	1		
STA. 1068+15.00	RT	85.25		1	
STA. 1068+35.00					1
STA. 1069+05.00	RT	55.23	1		
STA. 1069+05.00	RT	85.23		1	
STA. 1070+50.00	LT	54.81	1		
STA. 1070+50.00	RT	55.19	1		
STA. 1071+98.43	LT	39.85	1		
STA. 1071+98.46	RT	40.15	1		
STA. 1076+10.40					1
STA. 1115+55.99					1
STA. 1116+66.09	RT	39.95	1		
STA. 1121+00.00	RT	39.97	1		
STA. 1121+00.00	LT	40.03	1		
STA. 1122+50.00	RT	49.98	1		
STA. 1122+50.00	LT	50.02	1		
STA. 1123+55.00					1
STA. 1125+00.00	RT	49.99	1		
STA. 1125+00.00	LT	50.01	1		
STA. 1126+50.00	LT	40.00	1		
STA. 1126+50.00	RT	40.00	1		
STA. 1129+70.82	LT	39.99	1		
STA. 1131+23.92					1
EX 1			1		
EX 2			1		
TOTAL			22	2	6