

PAVEMENT MARKING SCHEDULE

STATION	LENGTH	PAINT PAVEMENT MARKING LINE, 4"				RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	SHORT TERM PAVEMENT MARKING (3 APPL.)	TEMPORARY PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
		4" YELLOW SKIP DASH	4" YELLOW SKIP DASH & NO PASSING	4" DOUBLE SOLID YELLOW	4" WHITE EDGE LINES					
FAP 328 (US 45)	(FT)	(FT)	(FT)	(FT)	(FT)	(EACH)	(EACH)	(FT)	(FT)	(SQ FT)
+60.0 TO 21+64.8	2104.8	526.2			4209.6	26.3	26.3	574.0	4735.8	1578.6
21+64.8 TO 29+04.0	739.2		924.0		1478.4	9.2	9.2	201.6	2402.4	800.8
29+04.0 TO 32+20.8	316.8	79.2			633.6	4.0	4.0	86.4	712.8	237.6
32+20.8 TO 37+48.8	528.0		660.0		1056.0	6.6	6.6	144.0	1716.0	572.0
37+48.8 TO 40+65.6	316.8	79.2			633.6	4.0	4.0	86.4	712.8	237.6
40+65.6 TO 50+16.0	950.4		1188.0		1900.8	11.9	11.9	259.2	3088.8	1029.6
50+16.0 TO 52+80.0	264.0	66.0			528.0	3.3	3.3	72.0	594.0	198.0
52+80.0 TO 60+19.2	739.2		924.0		1478.4	9.2	9.2	201.6	2402.4	800.8
60+19.2 TO 79+72.8	1953.6	488.4			3907.2	24.4	24.4	532.8	4395.6	1465.2
79+72.8 TO 85+53.6	580.8		726.0		1161.6	7.3	7.3	158.4	1887.6	629.2
85+53.6 TO 89+76.0	422.4	105.6			844.8	5.3	5.3	115.2	950.4	316.8
89+76.0 TO 95+56.8	580.8		726.0		1161.6	7.3	7.3	158.4	1887.6	629.2
95+56.8 TO 123+02.4	2745.6	686.4			5491.2	34.3	34.3	748.8	6177.6	2059.2
123+02.4 TO 130+41.6	739.2		924.0		1478.4	9.2	9.2	201.6	2402.4	800.8
130+41.6 TO 133+05.6	264.0	66.0			528.0	3.3	3.3	72.0	594.0	198.0
133+05.6 TO 141+50.4	844.8		1056.0		1689.6	10.6	10.6	230.4	2745.6	915.2
141+50.4 TO 142+03.2	52.8	13.2			105.6	0.7	0.7	14.4	118.8	39.6
142+03.2 TO 152+59.2	1056.0		1320.0		2112.0	13.2	13.2	288.0	3432.0	1144.0
152+59.2 TO 153+12.0	52.8			105.6	105.6	0.7	0.7	14.4	211.2	70.4
153+12.0 TO 164+84.6	1168.8		1461.0		2337.6	14.6	14.6	318.8	3798.6	1266.2
164+84.6 TO 170+65.4	580.8	145.2			1161.6	7.3	7.3	158.4	1306.8	435.6
170+65.4 TO 180+34.0	950.4		1188.0		1900.8	11.9	11.9	259.2	3088.8	1029.6
180+34.0 TO 190+90.0	1056.0		1320.0		2112.0	13.2	13.2	288.0	3432.0	1144.0
190+90.0 TO 256+93.1	6600.0	1650.0			13200.0	82.5	82.5	1800.0	14850.0	4950.0
256+93.1 TO 265+37.9	844.8		1056.0		1689.6	10.6	10.6	230.4	2745.6	915.2
265+37.9 TO 270+65.9	528.0			1056.0	1056.0	6.6	6.6	144.0	2112.0	704.0
270+65.9 TO 281+76.8	1056.0		1320.0		2112.0	13.2	13.2	288.0	3432.0	1144.0
281+76.8 TO 291+80.0	1003.2		1254.0		2006.4	12.5	12.5	273.6	3260.4	1086.8
291+80.0 TO 296+55.2	475.2	118.8		950.4	950.4	5.9	5.9	129.6	2019.6	673.2
296+55.2 TO 307+63.2	1003.2		1254.0		2006.4	12.5	12.5	273.6	3260.4	1086.8
307+63.2 TO 315+55.2	792.0	198.0			1584.0	9.9	9.9	216.0	1782.0	594.0
315+55.2 TO 321+88.8	633.6		792.0		1267.2	7.9	7.9	172.8	2059.2	686.4
321+88.8 TO 325+58.4	369.6	92.4			739.2	4.6	4.6	100.8	831.6	277.2
325+58.4 TO 334+03.2	844.8		1056.0		1689.6	10.6	10.6	230.4	2745.6	915.2
334+03.2 TO 355+00.0	2096.8	524.2			4193.6	26.2	26.2	571.9	4717.8	1572.6
SUBTOTAL - RURAL SECTION			26100		70511	441	441	9616	96611	32204
355+00.0 TO 381+53.0	2653.0	663.3			5306.0	33.2	33.2	1360.3	5969.3	1989.8
SUBTOTAL - URBAN SECTION			664		5306	34	34	1361	5970	1990
TOTALS			102581			475	475	10977	102581	34194