



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 26, 2009

SUBJECT: FAS 40 (Rock Grove Road)
Project SR-0040(113)
Section 05-00169-00-RS
Stephenson County
Contract No. 85426
Item 145
March 6, 2009 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Revised page 1 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by the letters "P.E." in a smaller font.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation



The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction", Adopted January 1, 2007, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways", and the "Manual of Test Procedures of Materials" in effect on the date of invitation of bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included here in which apply to and govern the construction of Section 05-00169-00-RS, Stephenson County, and in case of conflict with any part, Or parts, of said Specifications, the said Special Provisions shall take precedence and shall govern.

DESCRIPTION OF WORK

The proposed improvements shall consist of constructing a 6" cold in-place recycled asphalt base by pulverizing and rotomixing the existing 21' wide bituminous concrete surface. A 22' wide HMA Surface Course Overlay shall be placed on the recycled base with 5' aggregate wedge shoulders.

RECYCLED BASE

This work shall consist of the in-place recycling of the existing pavement by pulverizing and rotomixing the existing bituminous surface and shaping and compacting the mixture.

Materials

The gradation of the milled material shall be:

<u>Sieve Size</u>	<u>% Passing</u>
1"	95+/-5
1/2"	60+/-15

Equipment

Equipment shall meet the requirements of the following Articles of Section 1100.

<u>ITEMS</u>	<u>ARTICLE</u>
A. Rollers (Note 1)	1101.01
B. Graders	1101.05
C. Road Reclaimer (Note 2)	

Note 1: Rollers shall be a combination of Tamping "Padded Foot" or Pneumatic Tired and Steel Wheel capable of deriving the required compaction.

Note 2: The Contractor shall furnish a Road Reclaimer with milling drum capable of pulverizing and rotomixing the asphalt surface and aggregate base course into a homogenous mixture of the specified size. The Reclaimer shall be self-propelled with a recommended minimum 400 HP. The machine shall be capable of reclaiming not less than 8 ft. wide in each pass.

Staking

To ensure that control of Horizontal Alignment is maintained, the Contractor shall set an offset line prior to commencement of operations. The centerline will be established and points will be set at approximately 100 foot intervals by the County prior to the start of construction.

Method of Measurement

When the project is constructed essentially to the lines, grades, or dimensions shown in the plans, and the Contractor and the Engineer have agreed in writing that if the plan quantities are accurate, no further measurements will be required and payment will be made for the quantities shown in the contract for the various items involved, except that if errors are discovered after work has started, appropriate adjustments will be made.

Basis of Payment

This work shall be paid for at the contract unit price per SQUARE YARD for RECYCLED BASE, 6". These items shall include all labor and equipment for **offsetting centerline**, milling, pulverizing, mixing, watering, shaping and compaction of the base.

Revised 2-26-09