

EARTHWORK SCHEDULE

SCHEDULES

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5154	04-00343-00-BR	WINNEBAGO	92	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	EARTH EXCAVATION (SPECIAL) 20200100*	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25%	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) FURNISHED EXCAVATION 20400800
BELTLINE ROAD STA. 123+35.60 TO 154+37.00	207	155	16,952	-16,797
ILLINOIS RAILNET BRIDGE WEST ABUT. - STA. 147+25.59 EAST ABUT. - STA. 149+10.41			532 415	-332 -415
TOTALS	207	155	17,899	-17,744

SEEDING, CLASS 2		
STATION	ACRE	REMARKS
L 123+35.60 - 154+50.00	2.05	TO CONST. LIMITS - SEE CROSS SECTIONS
R 123+35.60 - 148+45.77	2.00	TO CONST. LIMITS - SEE CROSS SECTIONS
R 152+55.88 - 154+50.00	0.23	TO CONST. LIMITS - SEE CROSS SECTIONS
PROJECT TOTAL	4.28	

25000200

PHOSPHUROUS FERTILIZER NUTRIENT		
STATION	POUND	REMARKS
L 123+35.60 - 154+50.00	185	90* / ACRE
R 123+35.60 - 154+50.00	236	90* / ACRE
PROJECT TOTAL	421	

25000500

TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
STATION	UNIT	REMARKS
29' R 125+65	6	
32' R 126+13	6	
31' R 127+13	14	
18' L 128+33	7	
25' R 130+98	6	
26' R 131+28	12	
PROJECT TOTAL	51	

20100110

SEEDING, CLASS 4A		
STATION	ACRE	REMARKS
R 148+45.77 - 152+55.88	0.39	TO CONST. LIMITS - SEE CROSS SECTIONS
PROJECT TOTAL	0.39	

25000312

POTASSIUM FERTILIZER NUTRIENT		
STATION	POUND	REMARKS
L 123+35.60 - 154+50.00	185	90* / ACRE
R 123+35.60 - 154+50.00	236	90* / ACRE
PROJECT TOTAL	421	

25000600

TREE REMOVAL (OVER 15 UNITS DIAMETER)		
STATION	UNIT	REMARKS
68' R 136+12	36	
PROJECT TOTAL	36	

20100110

SEEDING, CLASS 5		
STATION	ACRE	REMARKS
R 148+45.77 - 152+55.88	0.39	TO CONST. LIMITS - SEE CROSS SECTIONS
PROJECT TOTAL	0.39	

25000320

MULCH METHOD 2		
STATION	ACRE	REMARKS
L 123+35.60 - 154+50.00	2.05	TO CONST. LIMITS - SEE CROSS SECTIONS
R 123+35.60 - 154+50.00	2.62	TO CONST. LIMITS - SEE CROSS SECTIONS
PROJECT TOTAL	4.67	

25100115

TREE REMOVAL, ACRES		
STATION	ACRES	REMARKS
L 131+93 - 136+94	0.39	
L 138+76 - 147+71	0.70	
L 148+07 - 152+78	0.45	
R 137+83 - 147+96	1.09	
R 149+17 - 151+91	0.27	
PROJECT TOTAL	2.90	

20100500

SEEDING, CLASS 7		
STATION	ACRE	REMARKS
L 123+35.60 - 154+50.00	2.05	TO CONST. LIMITS - SEE CROSS SECTIONS
R 123+35.60 - 154+50.00	2.62	TO CONST. LIMITS - SEE CROSS SECTIONS
PROJECT TOTAL	4.67	

25000350

EROSION CONTROL BLANKET		
STATION	SQ YD	REMARKS
L 141+50 - 146+50	333	6' WIDE
L 146+50 - 147+00	67	12' WIDE
R 134+90 - 137+10	293	12' WIDE
R 149+25 - 151+50	150	6' WIDE
PROJECT TOTAL	843	

25100630

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		
STATION	CU YD	REMARKS
CONTINGENCY ITEM	21	AS DIRECTED BY THE ENGINEER
PROJECT TOTAL	21	

20201200*

NITROGEN FERTILIZER NUTRIENT		
STATION	POUND	REMARKS
L 123+35.60 - 154+50.00	185	90* / ACRE
R 123+35.60 - 154+50.00	236	90* / ACRE
PROJECT TOTAL	421	

25000400

TEMPORARY DITCH CHECKS		
STATION	EACH	REMARKS
R 123+50	1	
R 125+00	1	
PROJECT TOTAL	2	

28000300