

SCHEDULES

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5154	04-00343-00-BR	WINNEBAGO	92	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

GUARDRAIL REMOVAL SPECIAL		
STATION	FOOT	REMARKS
L 127+14 - 128+13	99	
L 131+72 - 137+09	537	
L 139+81 - 147+17	736	
L 148+94 - 152+07	313	
R 126+97 - 127+95	98	
R 131+54 - 132+54	100	
R 140+03 - 147+41	738	
R 149+17 - 157+19	802	
PROJECT TOTAL	3,423	

X6320100*

PERIMETER EROSION BARRIER, SPECIAL		
STATION	FOOT	REMARKS
L 124+00 - 128+00	400	ALONG EXIST. R.O.W.
L 132+25 - 137+00	475	
L 137+00 - 137+30	35	
L 138+00	20	ALONG EXIST. R.O.W.
L 138+00 - 147+50	850	ALONG EXIST. R.O.W.
L148+20 - 152+58	444	ALONG EXIST. R.O.W.
L 152+58	20	ALONG EXIST. R.O.W.
L 153+38	25	ALONG EXIST. R.O.W.
L 153+38 - 153+50	20	
L 153+50 - 154+37	87	
R 122+30 - 122+70	77	
R 122+70 - 126+50	381	
R 126+50 - 127+00	50	
R 127+00 - 127+50	50	
R 131+50 - 137+30	580	
R 137+90 - 138+00	27	
R 138+00 - 139+00	100	
R 139+00 - 144+00	500	
R 144+00 - 148+00	400	
R 149+50 - 151+00	150	
R 151+00 - 154+37	333	
PROJECT TOTAL	5,024	

XX006285*

BITUMINOUS MIXTURE FOR PATCHING		
STATION	TON	REMARKS
CONTINGENCY ITEM	25	ON DETOUR ROUTE AS REQUIRED
PROJECT TOTAL	25	

Z0004800*

BREAKER-RUN CRUSHED STONE		
STATION	TON	REMARKS
CONTINGENCY ITEM	43	AS DIRECTED BY THE ENGINEER
PROJECT TOTAL	43	

Z0005400*

PLUG EXISTING CULVERTS		
STATION	EACH	REMARKS
L & R 141+73.98	2	12" CONC.
PROJECT TOTAL	2	

Z0041500*