

**INDEX OF SHEETS**

1 Cover Sheet  
 2-5 Index of Sheets & General Notes  
 6 Status of Utilities  
 7-9 Summary of Quantities

SECTION 1 - 54+95 TO 61+50  
 DESIGN ENGINEER: KEVIN HORST (309) 671-3472

10 Typical Sections  
 11 Schedule of Quantities  
 12 Existing & Removal  
 13 Proposed Plan  
 14 Proposed Pavement Marking Plan

SECTION 2 - 61+50 TO 88+89  
 LIAISON ENGINEER: NICK JACK (309) 671-3694  
 PLANS BY: COOMBE-BLOXDORF P.C.

15-17 Typical Sections (IL Rte 29)  
 18 Typical Sections (Relocated TR 103)  
 19-23 Schedule of Quantities  
 24 Reference Ties & Benchmarks  
 25 General Plan  
 26-28 Plan View IL Rte 29 & Relocated TR 103  
 29 Profile IL Rte 29  
 30 Profile Relocated TR 103  
 31 Profile Proposed Drainage Ditch  
 32 Plan & Profile TR 103 West (Wolcott ST.)  
 33 Plan & Profile TR 103B  
 34 Plan View Proposed Entrance  
 38 Traffic Control Plan  
 39-41 Erosion Control Plan  
 42-43 ROW Plan  
 44 Concrete Curb & Gutter and Gutter Elevation Detail  
 45 Pavement Marking Details  
 46-67 Structure Plans SN 072-0198  
 68-69 Culvert Extension Details  
 70 Unsuitable Excavation Treatment For Culvert Detail  
 71-109 Cross Sections IL 29  
 110-122 Cross Sections Relocated TR 103  
 123-124 Cross Sections TR 103 West (Wolcott St)  
 125-127 Cross Sections TR 103B (State St.)  
 128-129 Cross Sections Proposed Drainage Ditch  
 130-133 Bridge Approach Detail

SECTION 3 - 88+89 TO 286+40  
 DESIGN ENGINEER: MICHAEL HUDELSON (309) 671-3477

134-138 Typical Sections  
 139-142 Schedule of Quantities  
 143-149 Proposed Plan  
 150-156 Pavement Markings  
 157-160 Grating for Box Culvert with Wing Walls

161-186 District Standards

**GENERAL NOTES**

**SOIL REPORT AVAILABILITY**

All soils data collected and processed for the soils report made in conjunction with the design of this improvement is on file at the District Office where it is available for the inspection of Contractors or prospective bidders. By submitting a bid, the Contractor acknowledges that the Soils Report has been made available and is aware of the report contents and appendices.

**AVAILABILITY OF ELECTRONIC FILES**

Micro Station and GEOPAK files of this project will be made available to the Contractor. If there is a conflict between the electronic files and the printed contract plans and documents, the printed contract plans and documents shall take precedence over the electronic files. The Contractor shall accept all risk associated with using the electronic files and shall hold the Department harmless for any errors or omissions in the electronic files and the data contained therein. Errors or delays resulting from the use of the electronic files by the Contractor shall not result in an extension of time for any interim or final completion date or shall not be considered cause for additional compensation. The Contractor shall not use, share, or distribute these electronic files except for the purpose of constructing this contract. Any claims by third parties due to use or errors shall be the responsibility of the Contractor. The Contractor shall include this disclaimer with the transfer of these electronic files to any other parties and shall include appropriate language binding them to similar responsibilities.

**UTILITIES - LOCATIONS / INFORMATION ON PLANS**

The locations of existing water mains, gas mains, sewers, electric power lines, telephone lines and other utilities as shown on the plans are based on careful field investigation and the best information available, but they are not guaranteed. Unless elevations are shown — all utility locations shown on the cross sections are based on the approximate depth supplied by the utility company. It shall be the Contractor's responsibility to ascertain their exact location from the utility companies and by field inspection.

**TREE REMOVAL - UTILITY RELOCATION**

Tree removal may be necessary prior to utility companies being able to relocate their facilities outside the construction limits. The Contractor should coordinate any contract tree removal activities with the utility companies to eliminate conflicts and potential delays caused by utility tree removal activities or incomplete utility relocations.

FILE NAME = c:\projects\129mass\general.dgn	USER NAME = hudelsonm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS, GENERAL NOTES &amp; COMMITMENTS</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			64	10,121RS-6,11RS-4(10)BR	PEORIA	186	2	
		PLOT SCALE = 1/8"=1'-0" / IN.	CHECKED -			REVISED -	<b>CONTRACT NO. 88803</b>				
		PLOT DATE = 10/20/2008	DATE -			REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
						SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.	