

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		ROADWAY 80-20 FD/ST PEORIA CO. 1000	STRUCTURE 80-20 FD/ST PEORIA CO. X071-2A		CODE NO	ITEM	UNIT		ROADWAY 80-20 FD/ST PEORIA CO. 1000	STRUCTURE 80-20 FD/ST PEORIA CO. X071-2A	
50300300	PROTECTIVE COAT	SO YD	771		771		60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	65	65		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1		60602900	CONCRETE GUTTER, TYPE B (MODIFIED)	FOOT	362	362		
50500505	STUD SHEAR CONNECTORS	EACH	3105		3105		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	500	500		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	52150	1620	50530		63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	2325	2325		
50800515	BAR SPLICERS	EACH	411		411		63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	100	100		
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1442		1442		63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	9	9		
51202305	DRIVING PILES	FOOT	1442		1442		63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	3		
51203600	TEST PILE STEEL HP12X53	EACH	2		2		63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	13	13		
51205200	TEMPORARY SHEET PILING	SO FT	1049		1049		63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	1398	1398		
51300105	TEMPORARY BRIDGE COMPLETE	EACH	1		1		66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1		
51500100	NAME PLATES	EACH	1		1		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9		
52100520	ANCHOR BOLTS, 1"	EACH	60		60		67000600	ENGINEER'S FIELD LABORATORY	CAL MO	9	9		
54003000	CONCRETE BOX CULVERTS	CU YD	12.9	12.9			67100100	MOBILIZATION	L SUM	1	1		
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	77	77			70100400	TRAFFIC CONTROL AND PROTECTION, STANDARD 701431	EACH	1	1		
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	104	104			70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	102	102			70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	100	100			70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1	1		
542A5473	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	80	80			70102632	TRAFFIC CONTROL & PROTECTION, STANDARD 7 01602	L SUM	1	1		
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	46	46			70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	7	7			70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20		20	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	6	6			70106800	CHANGEABLE MESSAGE SIGN	CAL MO	9		9	
54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	1	1			70300100	SHORT-TERM PAVEMENT MARKING	FOOT	21382	21382		
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	114		114		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2746	2746		
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	235		235		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	109960	109960		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	12249	12249		
60236600	INLETS, TYPE A, TYPE 9 FRAME AND GRATE	EACH	1	1			70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	59	59		
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1	1			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	54	54		
60240400	INLETS, TYPE B, SPECIAL, WITH FRAME AND GRATE	EACH	1	1									
60246605	MEDIAN INLET (604101)	EACH	1	1									
60500060	REMOVING INLETS	EACH	6	6									
60600095	CLASS S1 CONCRETE (OUTLET)	CU YD	10.7	10.7									

• Specialty Item

FILE NAME c:\projects\1129\moss\general.dgn	USER NAME = hudelsonme	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			64	(10,12)RS-6(11)RS-4(10)BR	PEORIA	186	8	
	PLOT SCALE = 102.0000' / IN.	CHECKED -	REVISED -			<b>CONTRACT NO. 88803</b>					
	PLOT DATE = 10/20/2008	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					