

| PERMANENT AND TEMPORARY PAVEMENT MARKINGS | | | | | | | | | | | | RAISED REFLECTIVE PAVEMENT MARKERS | | |
|---|--------|----------------|--------------|-----------------|--------------|----------------|---------------|---------------------------|-------------|--|---------------------------|------------------------------------|------------------------|--|
| LOCATION | LENGTH | THERMOPLASTIC | | | | | | | | PREFORMED PLASTIC TY B 6" WHITE DASH CL FOOT | 1-WAY CRYSTAL CENTER EACH | 1-WAY CRYSTAL RTL EACH | 2-WAY AMBER TWLTL EACH | |
| | | 4" WHITE SOLID | | 4" YELLOW SOLID | | 4" YELLOW DASH | | LETTERS AND SYMBOLS SQ FT | | | | | | |
| | | LT FOOT | RT FOOT | MLT FOOT | MRT FOOT | MLT FOOT | MRT FOOT | | | | | | | |
| | | | | | | | | | | | | | | |
| 88+89 TO 95+20 | 631 | 631 | 631 | 631 | 631 | 157.75 | 157.75 | 124.8 | 316 | | | 32 | | |
| 95+20 TO 99+88 | 468 | 468 | 468 | 468 | 468 | | | | 234 | | | | | |
| 99+88 TO 104+82 | 494 | 494 | 494 | 494 | 494 | | | | 248 | | | | | |
| 104+82 TO 132+92 | 2810 | 2677 | 2617 | 2810 | 2810 | 702.5 | 702.5 | 468 | 1406 | | | 142 | | |
| 132+92 TO 137+63 | 471 | 471 | 471 | 471 | 471 | | | | 236 | | | | | |
| 137+63 TO 139+91 | 228 | 228 | 228 | 228 | 228 | 57 | 57 | 62.4 | 114 | | | 12 | | |
| 139+91 TO 143+66 | 375 | 375 | 375 | 375 | 375 | | | | 188 | | | | | |
| 143+66 TO 145+98 | 232 | 232 | 232 | 232 | 232 | 58 | 58 | 62.4 | 116 | | | 12 | | |
| 145+98 TO 152+76 | 678 | 678 | 678 | 678 | 678 | | | | 340 | | | | | |
| 152+76 TO 154+58 | 182 | 182 | 182 | 182 | 182 | | | | 92 | | | | | |
| 154+58 TO 157+21 | 263 | 263 | 526 | 263 | 263 | 65.75 | 65.75 | 109.2 | 132 | 7 | | 14 | | |
| 157+21 TO 162+92 | 571 | 571 | 471 | 571 | 571 | 142.75 | 142.75 | 93.6 | 286 | | | 30 | | |
| 162+92 TO 169+48 | 656 | 656 | 656 | 656 | 656 | | | | 328 | | | | | |
| 169+48 TO 176+06 | 658 | 658 | 558 | 658 | 658 | 164.5 | 164.5 | 124.8 | 330 | | | 34 | | |
| 176+06 TO 179+26 | 320 | 620 | 320 | 320 | 320 | | | 46.8 | 160 | 8 | | | | |
| 179+26 TO 181+50 | 224 | 224 | 224 | 224 | 224 | | | | 112 | | | | | |
| 181+50 TO 191+22 | 972 | 972 | 972 | 972 | 972 | | | | 486 | | | | | |
| 191+22 TO 211+41 | 2019 | 2019 | 3990 | 2019 | 2019 | 504.75 | 504.75 | 343.2 | 1010 | | | 102 | | |
| 211+41 TO 216+90 | 549 | 549 | 549 | 549 | 549 | | | | 276 | | | | | |
| 216+90 TO 228+44.5 (BK) | 1154.5 | 1154.5 | 1118.5 | 1154.5 | 1154.5 | 288.63 | 288.63 | 187.2 | 578 | | | 58 | | |
| 228+52.8 (AH) TO 229+32 | 79.2 | 79.2 | 79.2 | 79.2 | 79.2 | 19.8 | 19.8 | 31.2 | 40 | | | 4 | | |
| 229+32 TO 233+71 | 439 | 439 | 439 | 439 | 439 | | | | 220 | | | | | |
| 233+71 TO 240+62 | 691 | 607 | 627 | 691 | 691 | 172.75 | 172.75 | 124.8 | 346 | | | 36 | | |
| 240+62 TO 241+08 | 46 | 46 | 46 | 46 | 46 | 11.5 | 11.5 | 31.2 | 24 | | | 4 | | |
| 241+08 TO 242+60 | 152 | 152 | 152 | 152 | 152 | | | | 76 | | | | | |
| 242+60 TO 244+19 | 159 | 159 | 318 | 159 | 159 | | | 31.2 | 80 | 4 | | | | |
| 244+19 TO 245+37 | 118 | 118 | 236 | 118 | 118 | 29.5 | 29.5 | 46.8 | 60 | 3 | | 6 | | |
| 245+37 TO 248+92 | 355 | 355 | 355 | 355 | 355 | 88.75 | 88.75 | 62.4 | 178 | | | 18 | | |
| 248+92 TO 250+46 | 154 | 154 | 154 | 154 | 154 | | | | 78 | | | | | |
| 250+46 TO 274+83 | 2437 | 2385 | 2397 | 2437 | 2437 | 609.25 | 609.25 | 405.6 | 1220 | | | 122 | | |
| 274+83 TO 281+70 | 687 | 687 | 687 | 687 | 687 | | | | 344 | | | | | |
| 281+70 TO 286+11 | 441 | 441 | 441 | 441 | 441 | 110.25 | 110.25 | 93.6 | 222 | | | 24 | | |
| 286+11 TO 286+40 | 29 | 29 | 29 | 29 | 29 | | | | 16 | | | 2 | | |
| SUB TOTALS | | 19774 | 21721 | 19743 | 19743 | 3183.4 | 3183.4 | | | 495 | 22 | 652 | | |
| TOTALS | | | | 87347 | | | | 2449.2 | 9892 | | 1169 | | | |

| SHORT TERM PAVEMENT MARKING | | | | | | WORK ZONE PAVEMENT MARKING REMOVAL | |
|-----------------------------|--------|------------------|----------|------------|----------|------------------------------------|--|
| LOCATION | LENGTH | CL DASH | MED DASH | SHLDR DIAG | MED DIAG | SQ FT | |
| | | FOOT | FOOT | FOOT | FOOT | | |
| 88+89 TO 286+40 | 19751 | 3950 | 2546.7 | 1580 | 561 | | |
| | | 8637.7 | | | | | |
| | | X 2 APPLICATIONS | | | | | |
| TOTALS | | 17275.4 | | | | 5758.5 | |